DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	2.00 / 2.42	2.50 / 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	3.50 / 9.00	4.00 / 10.80	5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
BRADFORD US5 SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	W16-9FYG	30	18								1																
		F	S4-3P	36	12	F-Y-G		3.00																	REPLACE AHEAD WITH SCHOOL	X		
SB	3.650	F	D1-1E	72	12								1		X														
		F	D1-1	72	12			12.00								2		X									8	
SB	3.625	H	R1-1	30	30								1		X														
		H	R1-1	30	30			6.25								1		X									X		
SB	3.630	F	R8-3A	24	24								1		X														
		F	VR-644P	24	12			2.00								1		X										6	
		F	R8-3A	24	24			4.00																			X		
SB	3.595	F	R2-1	24	30								1		X														
		F	R2-1	24	30			5.00								1		X									X		
SB	3.570	F	R8-3A	24	24								1		X														
		F	R8-3A	24	24			4.00								1		X									X		
SB	3.525	F	R8-3A	24	24								1		X														
		F	R8-3A	24	24			4.00								1		X									X		
							SHEET TOTALS	40.25	0.00	0	0	0	7	0	0	7		105											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN TOTALS	531.1	0.0	13.0	4.0	4.0	95	0.0	0.0	85		1275.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE NORTHEAST
PROJECT NUMBER: STPG SIGN (29)

FILE NAME: BRADFORD US5 SB
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: D. CROSSLEY
BRADFORD US 5 SB 3

PLOT DATE: 8/18/2010
DRAWN BY: D. CROSSLEY
CHECKED BY: A. GAMBLE
SHEET 122 OF 138