DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WILLISTON NORTHBOUND							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		A	M3-2	24	12		EAST						1																
		A	M1-4	24	24		US 2						1																
		A	M6-1	21	15		RIGHT						1																
NB	3.705	A	OM1-1	18	18								1		X														
		A	OM1-1	18	18			2.25								1		X									X		
NB	3.730	A	M3-4	24	12			2.00								2		X								#3	BLACK ON WHITE SHEETING. INSTALL ACROSS FROM INTERSECTION, BETWEEN TRAFFIC SIGNAL POLE AND PEDESTRIAN LIGHT	X		
		A	M1-4	24	24			4.00																				
		A	M6-1L	21	15			2.19																		BLACK ON WHITE SHEETING	X		
		A	M3-1	24	12			2.00																			GREEN ON WHITE SHEETING	X		
		A	M1-5A	24	24			4.00																						E-136B
		A	M6-3	21	15			2.19																			GREEN ON WHITE SHEETING	X		
		A	M3-2	24	12			2.00																			BLACK ON WHITE SHEETING	X		
		A	M1-4	24	24			4.00																						
		A	M6-1R	21	15			2.19																			BLACK ON WHITE SHEETING	X		
NB	3.740	A	M3-1S	24	12								1		X														
							SHEET TOTALS	26.82	0.00	0	0	0	5	0	0	3		45											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN DIRECTIONAL TOTALS	434.7	0.0	26.0	1.0	1.0	90	0.0	0.0	69		1035.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Statewide - Northwest Region**
PROJECT NUMBER: **STPG SIGN(30)**

FILE NAME: **Williston NB.xls** PLOT DATE: **8/11/2010**
PROJECT MANAGER: **A. Gamble** DRAWN BY: **T. Guazzoni**
DESIGNED BY: **T. Guazzoni** CHECKED BY: **A. Gamble**
WILLISTON VT 2A NB SHEET 8 SHEET **16** OF **131**