DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WILLISTON SOUTHBOUND							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHS"-STANDARD HIGHWAY SIGNS			
		F	M3-3	24	12		Hinesburg 9	2.00																	GREEN ON WHITE SHEETING	X		
		F	M1-5A	24	24		Bristol 26	4.00																				E-136B
		F	M4-5	24	12		SOUTH TO	2.00																	WHITE ON BLUE SHEETING	X		
		F	M1-1	24	24		VERMONT 2A INTERSTATE 89	4.00																		X		
SB	3.655	F	VR-934	48	30		LEFT ONLY/THRU/THRU & RIGHT						1		X													
SB	3.641	F	VR-934	48	30		ONLY	10.00								2		X							INSTALL SIGN 60' +/- NORTH OF EXISTING DESTINATION SIGNS			E-145B
SB	3.631	F	D2-1	72	10		DESTINATION SIGN						1		X													
		F	D1-1A	72	10		DESTINATION SIGN						1															
SB	3.51	F	R2-1	24	30		SPEED LIMIT 35						1	X														
		F	R2-1	24	30			5.00																		X		
SB	3.390	F	VR-934	48	30		ONLY						1	X														
		F	VR-934	48	30			10.00								2		X										E-145B
SB	3.340	G	VR-079	24	30		LEGAL LOAD AS FOR STATE HIGHWAYS	5.00								1		X							MARSHALL AVE (TH-6)			E-141
SB	3.31	F	M3-3S	24	12								1		X													
		F	M1-5	24	24								1															
							SHEET TOTALS	42.00	0.00	0	0	0	7	0	0	5		75										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN DIRECTIONAL TOTALS	472.7	0.0	20.0	1.0	1.0	84	0.0	0.0	67		1005.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: Statewide - Northwest Region
PROJECT NUMBER: STPG SIGN(30)

FILE NAME: Williston SB.xls
PROJECT MANAGER: A. Gamble
DESIGNED BY: T. Guazzoni
WILLISTON VT 2A SB SHEET 11

PLOT DATE: 8/11/2010
DRAWN BY: T. Guazzoni
CHECKED BY: A. Gamble
SHEET 33 OF 131