DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 / 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 / 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 / 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 / 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 / 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 / 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 / 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
ADDISON EASTBOUND							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		A	M7-4L	12	9		LEFT DIAGONAL ARROW					1																
EB	2.38 TO 2.58			6	8		22 WHITE DELINEATORS	3.67								11	X									INSTALL B-B ON 11 POSTS AT 100' SPACING, START 50' +/- EAST OF RELOCATED CHAMPLAIN BIKEWAY SIGN		5	
EB	3.366	D	R1-1	30	30		STOP			1				X												CHURCH ST (TH-32)			
EB	3.371	C	VR-017	24	30		LEGAL LOAD LIMIT 24000 LBS			1				X												CHURCH ST (TH-32)			
EB	3.761	C	VR-017	24	24								1		X														
		C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS	5.00								1		X								JERSEY ST SOUTH (TH-2)			E-141
EB	3.769	D	R1-1	30	30		STOP			1				X												JERSEY ST SOUTH (TH-2)			
EB	3.788	A	M3-2S	24	12		EAST			1				X															
		A	M1-5	24	24		VERMONT ROUTE 17			1																			
EB	3.831	A	VW-619	30	30		SHOULDER NARROWS				1	1			X	2		X											
EB	4.508	A	W1-10R	30	30								1		X														
		A	W13-1	18	18								1																
		A	W1-10R	36	36	FY	35 M.P.H.	9.00								2		X									X		
		A	W13-1	24	24	FY		4.00																			X		
EB	5.250	A	W1-4L	30	30		LEFT REVERSE CURVE						1		X														
							SHEET TOTALS	21.67 SF	0.00 SF	5 EA	1 EA	2 EA	4 EA	0 EA	0 EA	16 EA	240 FT												
							TOWN DIRECTIONAL TOTALS	418.6	0.0	38.0	7.0	7.0	65	0.0	0.0	69	1035.0												

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Statewide - Northwest Region**
PROJECT NUMBER: **STPG SIGN(30)**

FILE NAME: **Addison EB.xls** PLOT DATE: **8/11/2010**
PROJECT MANAGER: **A. Gamble** DRAWN BY: **T. Guazzoni**
DESIGNED BY: **T. Guazzoni** CHECKED BY: **A. Gamble**
ADDISON VT17 EASTBOUND SHEET 3 SHEET **39** OF **131**