DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
ADDISON EASTBOUND							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		A	W13-1	18	18		35 MPH PLAQUE						1																
EB	9.130	A	W11-6	30	30								1		X														
		A	W11-6H	30	30			6.25								1		X									HINGED SIGN, INSTALL IN CLOSED POSTION			E-153
EB	9.168	A	W1-10L	36	36			9.00								2		X									INSTALL 200' +/- EAST OF SNOWMOBILE SIGN	X		
		A	W13-1	24	24			4.00																				X		
EB	9.175	A	W1-6L	48	24		LARGE ARROW			1				X																
EB	9.180	B	W1-6R	48	24								1		X															
		B	W1-6R	48	24			8.00								2		X										X		
EB	9.210	D	R1-1	24	24		STOP						1		X															
		C	VR-017	24	24		LEGAL LOAD LIMIT 24000 LBS						1																	
EB	9.215	D	R1-1	30	30			6.25								1		X									INSTALL IN GRASSED MEDIAN. MOUNTAIN RD (TH-5)	X		
EB	9.215	C	VR-017	24	30			5.00								1											INSTALL AT BASE OF GRASSED MEDIAN. MOUNTAIN RD (TH-5)			E-141
EB	9.240	D	R1-1	30	30								2 1		X															
		D	R1-1	30	30			6.25								1		X									MOUNTAIN RD (TH-5)	X		
EB	9.440	A	R2-1	24	30		SPEED LIMIT 45			1				X																
SIGN SUMMARY SHEET							SHEET TOTALS	44.75	0.00	2	~~0~~	~~0~~	~~5~~ 6	0	0	7			105										
								SF	SF	EA	EA	EA	EA	EA	EA	EA			FT										
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	418.6	0.0	38.0	7.0	7.0	65	0.0	0.0	69			1035.0										

PROJECT NAME: **Statewide - Northwest Region**
PROJECT NUMBER: **STPG SIGN(30)**

FILE NAME: **Addison EB.xls** PLOT DATE: **8/11/2010**
PROJECT MANAGER: **A. Gamble** DRAWN BY: **T. Guazzoni**
DESIGNED BY: **T. Guazzoni** CHECKED BY: **A. Gamble**
ADDISON VT17 EASTBOUND SHEET 10 SHEET **46** OF **131**