DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)					SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT) 1.88	2.00 (LB / FT) 2.42	2.50 (LB / FT) 3.35	FOUNDATION	3.00 (LB / FT) 7.60	3.50 (LB / FT) 9.00	4.00 (LB / FT) 10.80	5.00 (LB / FT) 14.60			DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
ADDISON WESTBOUND							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	M6-3S	21	15		^UP ARROW			1																		
		F	M3-1S	24	12		NORTH			1																		
		F	M1-5	30	24		VERMONT 22A			1																		
		F	M6-1S	21	15		RIGHT --->			1																		
WB	8.409	F	R1-1	48	48								1	X														
		F	R1-1	48	48			16.00																		RETAIN FLASHING BEACONS	X	
WB	8.343	F	S1-1	36	36		SCHOOL			1				X														
		F	W16-9	24	12		AHEAD			1																		
WB	8.332	F	R8-3A	24	24								1		X													
		F	VR-644P	24	12								1															
		F	VR-644P	24	12			2.00																		RED ON WHITE SHEETING		5
		F	R8-3A	24	24			4.00								1	X										X	
WB	8.304	F	R8-3A	24	24								1		X													
		F	M4-6P	24	12								1															
		F	M4-6P	24	12			2.00																		RED ON WHITE SHEETING	X	
SIGN SUMMARY SHEET							SHEET TOTALS	24.00	0.00	6	0	0	5	0	0	1		15										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	296.9	0.0	34.0	6.0	6.0	50	0.0	0.0	51		765.0										

PROJECT NAME: **Statewide - Northwest Region**
PROJECT NUMBER: **STPG SIGN(30)**

FILE NAME: **Addison WB.xls** PLOT DATE: **8/11/2010**
PROJECT MANAGER: **A. Gamble** DRAWN BY: **T. Guazzoni**
DESIGNED BY: **T. Guazzoni** CHECKED BY: **A. Gamble**
ADDISON VT 17 WESTBOUND SHEET 4 SHEET **53** OF **131**