DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
ADDISON WESTBOUND							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
WB	0.710	F	R2-5A	24	30								1		X														
		F	W3-5	36	36			9.00								2		X									X		
WB	0.560	F	R2-1	24	30								1		X														
		F	R2-1	30	36			7.50								1		X										6	
WB	0.510	F	M2-1S	21	15								1		X														
		F	M1-5	30	24								1																
		F	M2-1	21	15			2.19								1		X								GREEN ON WHITE SHEETING	X		
		F	M1-5	30	24			5.00																					E-136B
							SHEET TOTALS	23.69	0.00	0	0	0	4	0	0	4		60											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN DIRECTIONAL TOTALS	~~296.9~~ 730.80	~~0.0~~	34.0	~~6.0~~ 15	~~6.0~~	~~50~~ 111.0	0.0	0.0	51		~~765.0~~ 1544.75											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: Statewide - Northwest Region
PROJECT NUMBER: STPG SIGN(30)

FILE NAME: Addison WB.xls
PROJECT MANAGER: A. Gamble
DESIGNED BY: T. Guazzoni
ADDISON VT 17 WESTBOUND SHEET 10

PLOT DATE: 8/11/2010
DRAWN BY: T. Guazzoni
CHECKED BY: A. Gamble