DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)					SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL		
																	1.75	2.00	2.50		3.00	3.50	4.00	5.00					
																	(LB / FT)				(LB / FT)								
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.88	2.42	3.35	FOUNDATION	7.60	9.00	10.80	14.60			DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
CORNWALL EASTBOUND							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		A	M6-1S	21	15								1																
		A	M3-3S	24	12								1																
		A	M1-5	24	24								1																
		A	M6-1S	21	15								1																
		A	M3-1	24	12			2.00								2		X							#2	GREEN ON WHITE SHEETING	X	7	
		A	M1-5	24	24			4.00																					E-136B
		A	M6-1	21	15			2.19																	GREEN ON WHITE SHEETING	X		
		A	M3-3	24	12			2.00																		GREEN ON WHITE SHEETING	X		
		A	M1-5	24	24			4.00																					E-136B
		A	M6-1S	21	15			2.19																		GREEN ON WHITE SHEETING	X		
EB	2.866	A	D9-1A	24	30		PHONE						1		X														
EB	2.870	A	R1-1	30	30		STOP			1				X												INTERSECTION TO BE RECONFIGURED BY PAVING PROJECT			
EB	2.880	J	R1-1	30	30		STOP			1				X												INTERSECTION TO BE RECONFIGURED BY PAVING PROJECT. LOCATED IN GRASS MEDIAN			
							SHEET TOTALS	16.38	0.00	2	0	0	5	0	0	2			30									
								SF	SF	EA	EA	EA	EA	EA	EA	EA			FT									
							TOWN DIRECTIONAL TOTALS	115.2	0.0	7.0	0.0	0.0	24	0.0	0.0	18			270.0									

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Statewide - Northwest Region**
PROJECT NUMBER: **STPG SIGN(30)**

FILE NAME: **Cornwall EB.xls** PLOT DATE: **8/11/2010**
PROJECT MANAGER: **A. Gamble** DRAWN BY: **T. Guazzoni**
DESIGNED BY: **T. Guazzoni** CHECKED BY: **A. Gamble**
CORNWALL VT 74 EASTBOUND SHEET 4 SHEET **63** OF **131**