DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
CORNWALL WESTBOUND							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	W1-2L	30	30		LEFT CURVE AHEAD					~~1~~				~~1~~		~~X~~								RELOCATED FROM MP 0.256			
		F	W13-1	18	18		40 MPH PLAQUE					~~1~~																	
WB	0.078	F	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X														
WB	0.020	G	VD-024	72	12		CORNWALL/SHOREHAM						1		X														

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

	NEW SIGNS "A"	NEW SIGNS "B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	POST RETAIN	POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL
SHEET TOTALS	0.00	0.00	0	0	2	2	0	0	1	15
	SF	SF	EA	EA	EA	EA	EA	EA	EA	FT
TOWN DIRECTIONAL TOTALS	175.41 ~~60.3~~	0.0	5.0	~~2.0~~	5.0 ~~2.0~~	35.0 ~~13~~	0.0	0.0	10	421.25 ~~150.0~~

PROJECT NAME: **Statewide - Northwest Region**
PROJECT NUMBER: **STPG SIGN(30)**

FILE NAME: **Cornwall WB.xls** PLOT DATE: **8/11/2010**
PROJECT MANAGER: **A. Gamble** DRAWN BY: **T. Guazzoni**
DESIGNED BY: **T. Guazzoni** CHECKED BY: **A. Gamble**
CORNWALL VT 74 WESTBOUND SHEET 3 SHEET **66** OF **131**