DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
MIDDLEBURY NORTHBOUND							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		A	S3-1	36	36	FYG		9.00																	RETAIN POST, FLASHING BEACON MISSING	X		
NB	4.34 TO 4.38			6	8		10 WHITE DELINEATORS	3.33								5	X									INSTALL B-B ON 5 POSTS, 50' SPACING, BEGINNING 740' +/- NORTH OF EXISTING RIGHT REVERSE CURVE ASSEMBLY		5	
NB	4.480	B	W1-4MR	30	30		MODIFIED RIGHT REVERSE CURVE						1		X													
		B	W13-1	18	18		35 MPH PLAQUE						1															
NB	4.760	A	VW-081R	30	30		TRUCKS ENTERING RIGHT						1		X													
NB	4.845	A	VW-081R	30	30			6.25								1		X							INSTALL 450' +/- NORTH OF EXISTING TRUCKS ENTERING RIGHT SIGN		7	
NB	4.970	A	W1-2L	30	30			6.25								1		X									INSTALL 100' +/- SOUTH OF GRAVEL PIT DRIVE	X		
NB	5.310	A	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X													
NB	6.215	A	W1-2R	30	30								1		X													
		A	W1-2R	30	30			6.25								1		X										X		

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

SHEET TOTALS	31.08	0.00	0	0	0	5	0	0	8	120						
	SF	SF	EA	EA	EA	EA	EA	EA	EA	FT						
TOWN DIRECTIONAL TOTALS	330.0	0.0	10.0	1.0	1.0	62	0.0	0.0	46	690.0						

PROJECT NAME: **Statewide - Northwest Region**
PROJECT NUMBER: **STPG SIGN(30)**

FILE NAME: **Middleburv EB.xls**
PROJECT MANAGER: **A. Gamble**
DESIGNED BY: **T. Guazzoni**
MIDDLEBURY VT116 NB SHEET 10

PLOT DATE: **8/11/2010**
DRAWN BY: **T. Guazzoni**
CHECKED BY: **A. Gamble**
SHEET **76** OF **131**