DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL		
																	1.75	2.00	2.50	3.00	3.50	4.00	5.00					
																	(LB / FT)			(LB / FT)							
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.88	2.42	3.35	FOUNDATION	7.60	9.00	10.80	14.60			DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
BRISTOL NORTHBOUND							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHS"-STANDARD HIGHWAY SIGNS			
NB	3.265	A	W1-10MaR	30	30		MODIFIED RIGHT TURN			1				X														
		A	W13-1	18	18		25 MPH PLAQUE			1																		
NB	3.31	A	VW-207A	24	18		BLIND PERSON			1				X														
		A	W13-1	18	18		25 MPH PLAQUE			1																		
NB	3.92	A	W11-7	30	30		EQUESTRIAN						1		X													
NB	4.14	A	W11-5	30	30		FARM EQUIPMENT			1				X														
NB	4.894	C	VR-017	24	30								1		X														
		C	VR-017	24	30			5.00								1		X								HEWITT RD (TH-5), INSTALL NEW SIGN ACROSS FROM STOP SIGN			E-141
NB	4.905	D	R1-1	30	30								1		X														
		D	R1-1	30	30			6.25								1		X								HEWITT RD (TH-5)	X	
NB	4.944	A	M3-1S	24	12								1		X													
		A	M1-5	30	24								1															
		A	M3-1	24	12			2.00								1		X								GREEN ON WHITE SHEETING	X	
		A	M1-5	30	24			5.00																				E-136B
NB	5.05	A	VW-081R	30	30								1		X													
							SHEET TOTALS	18.25	0.00	5	0	0	6	0	0	3		45										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN DIRECTIONAL TOTALS	348.6	0.0	46.0	1.0	1.0	69	0.0	0.0	56		840.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Statewide - Northwest Region**
PROJECT NUMBER: **STPG SIGN(30)**

FILE NAME: **Bristol NB.xls** PLOT DATE: **8/11/2010**
PROJECT MANAGER: **A. Gamble** DRAWN BY: **T. Guazzoni**
DESIGNED BY: **T. Guazzoni** CHECKED BY: **A. Gamble**
BRISTOL VT 116 NORTHBOUND SHEET 3 SHEET **90** OF **131**