DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
BRISTOL NORTHBOUND							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	9.93	A	D2-1	72	10								1		X													
		A	D2-1	72	10								1															
		A	D2-1	72	12		Starksboro 5 Hinesburg 14	6.00								2		X										5	
		A	D2-1	72	12			6.00																				5	
NB	10.00	A	R2-1	24	30		SPEED LIMIT 50 MM						1		X													
		A	R2-1	24	30			5.00				I				1		X									X	
NB	10.86	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS						1		X													
		C	VR-017	24	30			5.00								1		X								MEEHAN RD (TH-11), REMOVE TOWN NEIGHBORHOOD WATCH SIGN, RETURN TO TOWN		E-141
NB	10.865	D	R1-1	30	30		STOP						1		X													
		D	R1-1	30	30			6.25								1		X								MEEHAN RD (TH-11)	X	
NB	11.11	A	W11-3A	30	30			6.25								1		X								INSTALL ASSEMBLY 400' +/- SOUTH OF DRIVE #3024	X	
		A	W7-3A	24	18		NEXT 1 MILE	3.00																			X	
NB	12.232	A	W11-6H	30	30		HINGED SNOWMOBILE SIGN						1		X													
							SHEET TOTALS	37.50 SF	0.00 SF	0 EA	0 EA	0 EA	6 EA	0 EA	0 EA	6 EA	90 FT											
							TOWN DIRECTIONAL TOTALS	348.6	0.0	46.0	1.0	1.0	69	0.0	0.0	56	840.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Statewide - Northwest Region**
PROJECT NUMBER: **STPG SIGN(30)**

FILE NAME: **Bristol NB.xls** PLOT DATE: **8/11/2010**
PROJECT MANAGER: **A. Gamble** DRAWN BY: **T. Guazzoni**
DESIGNED BY: **T. Guazzoni** CHECKED BY: **A. Gamble**
BRISTOL VT 116 NORTHBOUND SHEET 13 SHEET **100** OF **131**