DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT) 1.88	2.00 (LB / FT) 2.42	2.50 (LB / FT) 3.35	FOUNDATION	3.00 (LB / FT) 7.60	3.50 (LB / FT) 9.00	4.00 (LB / FT) 10.80	5.00 (LB / FT) 14.60			DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
BRISTOL SOUTHBOUND							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHS"-STANDARD HIGHWAY SIGNS			
SB	3.170	F	VW-005	30	30		BRIDGES FREEZE BEFORE ROAD			1				X														
SB	3.175	F	OM-3R	12	36		RIGHT OBJECT MARKER			1				X														
SB	3.140	E	OM-3L	12	36		LEFT OBJECT MARKER			1				X														
SB	2.725	F	W1-2L	30	30			6.25								1		X								INSTALL 400' +/- NORTH OF DRIVE #2852	X		
SB	2.518	G	VR-017	24	30								1		X														
		G	VR-017	24	30			5.00								1		X								COVE RD (TH-26)			E-141
SB	2.511	H	R1-1	30	30							I	1		X														
		H	R1-1	30	30			6.25								1		X								COVE RD (TH-26)	X		
SB	2.500	F	M1-5A	24	24		VERMONT 116						2 ~~1~~		X														
		F	M6-2	21	15		<=== LEFT (45 DEG)						1																
		E	M1-5A	24	24		VERMONT 116						1																
		E	M6-2	21	15		RIGHT ===> (45 DEG)						1																
SB	1.620	F	S3-1	36	36	FYG		9.00								2		X								INSTALL 105' +/- NORTH OF EXISTING SCHOOL BUS STOP AHEAD SIGN	X		
SB	1.600	F	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X														
SB	1.200	F	R2-1	24	30			5.00								1		X								INSTALL 80' +/- SOUTH OF DRIVE #4300	X		
							SHEET TOTALS	31.50	0.00	3	0	I ~~0~~	8 ~~7~~	0	0	6		90										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN DIRECTIONAL TOTALS	322.5	0.0	41.0	2.0	2.0	70	0.0	0.0	49		735.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **Statewide - Northwest Region**
PROJECT NUMBER: **STPG SIGN(30)**

FILE NAME: **Bristol SB.xls** PLOT DATE: **8/11/2010**
PROJECT MANAGER: **A. Gamble** DRAWN BY: **T. Guazzoni**
DESIGNED BY: **T. Guazzoni** CHECKED BY: **A. Gamble**
BRISTOL VT 116 SOUTHBOUND SHEET 12 SHEET **112** OF **131**