DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)					SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75 (LB / FT) 1.88	2.00 (LB / FT) 2.42	2.50 (LB / FT) 3.35	FOUNDATION	3.00 (LB / FT) 7.60	3.50 (LB / FT) 9.00	4.00 (LB / FT) 10.80	5.00 (LB / FT) 14.60			DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
ESSEX WESTBOUND							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
WB	4.110	F	W3-5	36	36		SPEED REDUCTION 45 MPH			1				X														
WB	3.990	F	R2-1	30	36								1		X														
		F	R2-1	30	36			7.25								1		X									6	
WB	3.860	F	VW-202	30	30								1	X														
		F	VW-202	30	30			6.25																				E-154
WB	3.755	F	R2-1	24	30		SPEED LIMIT 45			1				X														
WB	3.570	F	N/A	N/A	N/A		EMPTY POST								X													
WB	3.520	F	VW-202	30	30		TRUCKS ENTERING						1		X													
WB	3.485	F	R2-1	24	30								1		X														
		F	R2-1	30	36			7.25								1		X									6	
WB	3.285	H	R1-1	30	30		STOP			1				X														
		G	VR-017	24	30		LEGAL LOAD LIMIT 24000 LBS			1				X														
WB	3.270	H	R1-1	30	30								1		X														
		H	R1-1	30	30			6.25								1		X								SAND HILL RD (TH-4)	X	
WB	3.230	H	R2-1	24	30								1		X													
SIGN SUMMARY SHEET							SHEET TOTALS	27.00	0.00	4	0	0	6	0	0	3		45										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	176.8	24.0	8.0	2.0	2.0	33	0.0	0.0	29		435.0				2.0	30.0					

PROJECT NAME: **Statewide - Northwest Region**
PROJECT NUMBER: **STPG SIGN(30)**
FILE NAME: **Essex EB.xls** PLOT DATE: **8/11/2010**
PROJECT MANAGER: **A. Gamble** DRAWN BY: **T. Guazzoni**
DESIGNED BY: **T. Guazzoni** CHECKED BY: **A. Gamble**
ESSEX VT 117 WESTBOUND SHEET 1 SHEET **123** OF **131**