DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
BRATTLEBORO EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN ✳ SEE NOTES																			"SHS"-STANDARD HIGHWAY SIGNS			
EB	0.000	C	VD-024	60	7.5								1		X													
		C	VD-700	6	8								1															
		C	VD-700	6	8								1															
		C	VD-024	72	10		Brattleboro | Marlboro *	5.00								2		12.75 12.75 X								INSTALL THE NEW SIGN IN THE SAME POSITION AS THE REMOVAL		4	
		C	VD-700	6	10		0090 1302 0000 * 0090 1311 0830 *	0.42																		BRATTLEBORO MILE MARKER; INSTALL ON THE LEFT POST		4	
		C	VD-700	6	10			0.42																		MARLBORO MILE MARKER; INSTALL ON THE RIGHT POST		4	
EB	0.015	C	VR-023B	24	30		$500 FINE FOR THROWING TRASH ON HIGHWAYS AND STREAMS *						1		X													
		C	VR-023B	24	30			5.00								1		13.25 X			SEE ABOVE						INSTALL PARALLEL TO VT-9 AT THE EDGE AND MIDPOINT ± OF THE PAVED PULLOUT		6	
EB	0.038	A	W1-5R	36	36		NEXT 4 MILES	9.00								2		14.25 14.25 X									INSTALL BEHIND RAIL 200 FT ± WEST OF THE TOWN LINE SIGN	X		
		A	W7-3A	24	18			3.00																			INSTALL PLAQUE ON LEFT SIDE POST	X		
EB	0.175	A	W1-1L	30	30		LEFT TURN SYMBOL						1		X												TO BE REPLACED 75 FT ± AHEAD			
		A	W13-1	18	18		30-MPH PLAQUE						1																	
EB	0.190	A	W1-1L	30	30			6.25			1	1	1			1		15.0 X			ON 8/28/11 THE "30 MPH" SIGN WAS DESTROYED AS WAS THE POST. BOTH ITEMS WERE REPLACED ON THE THIS PROJECT.						INSTALL BEHIND RAIL 75 FT ± EAST OF PREVIOUS POSITION	X		
		A	W13-1	24	24		30 MPH *	4.00✳										*15.0										X		
EB	0.230	A	W1-6	48	24								1		X						CURVE SIGN WAS REMOVED AND SLVAGED ON THE NEW POST								6	
							SHEET TOTALS	~~37.09~~ 33.09 SF	0.00 SF	0 EA	~~1~~ 0 EA	~~1~~ 0 EA	~~8~~ 7 EA	0 EA	0 EA	6 EA		~~97.5~~ 90 FT											
							TOWN DIRECTIONAL TOTALS	305.3	0.0	4.0	1.0	1.0	66	0.0	0.0	53		795.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STPG SIGN (31)

FILE NAME: BRATTLEBORO EASTBOUND
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: M. MILLER
BRATTLEBORO VT-9 EASTBOUND 1

PLOT DATE: 8/11/2010
DRAWN BY: M. MILLER
CHECKED BY: A. GAMBLE
SHEET 10 OF 175