









DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS UNLESS NOTED ALL MILE MARKERS WERE RE-INSTALLED ON THE NEW POSTS.	SIGN DETAIL			
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75	2.00	2.50	FOUNDATION	3.00	3.50	4.00			5.00	DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
																	(LB / FT)				(LB / FT)								
BRATTLEBORO EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																"SHS"-STANDARD HIGHWAY SIGNS						
EB	0.230	A	W1-6	48	24			8.00							2		13.0' 13.5'								INSTALL IN THE SAME POSITION AS THE REMOVAL	X			
EB	0.244	B	W1-6	48	24			8.00							2		11.5' 12.25'								FACES WB TRAFFIC; INSTALL BEHIND RAIL 75 FT ± EAST OF THE EB-FACING ARROW	X			
EB	0.308	A	W11-2	30	30		PEDESTRIAN (SYMBOL)	6.25																					
		A	W16-4	24	18		NEXT 1000 FT (PLAQUE)	5.00																					
		A	W11-2	30	30	FYG	 *	6.25							1		17.0' X								INSTALL IN SAME POSITION AS REMOVAL	X			
		A	W16-4	30	24	FYG	 *	5.00									14.75'								BOTH SIGNS HAVE FLUORESCENT YELLOW-GREEN BACKGROUND SHEETING	X			
EB	0.338	B	W1-6	48	24		LARGE ARROW RIGHT ==>>>																						
EB	0.419	A	W1-2R	30	30		RIGHT CURVE																		TO BE REPLACED FURTHER AHEAD				
		A	W13-1	18	18		40-MPH (PLAQUE)																						
EB	0.468	A	VS3-4	30	30		SCHOOL BUS TURN AROUND																		TO BE REPLACED FURTHER AHEAD				
		A	W1-2R	30	30			6.25							1		15.75' X										X		
		A	W13-1	18	18			2.25																			X		
EB	0.600	A	W1-2L	30	30		LEFT CURVE SYMBOL																						
		A	W13-1	18	18													13.0' 13.25'											
		A	VS3-4	36	36	FYG	 *	9.00							2		14.25' 15.0' X								FLUORESCENT YELLOW-GREEN BACKGROUND SHEETING			6	
SIGN SUMMARY SHEET							SHEET TOTALS	65.00 44.75	0.00	0	0	0	8	0	0	8		153.25 120							PROJECT NAME: STATEWIDE SOUTHEAST REGION				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	305.3	0.0	4.0	1.0	1.0	66	0.0	0.0	53		795.0						PROJECT NUMBER: STPG SIGN (31)					
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT						FILE NAME: BRATTLEBORO EASTBOUND	PLOT DATE: 8/11/2010				
																								PROJECT MANAGER: A. GAMBLE	DRAWN BY: M. MILLER				
																								DESIGNED BY: M. MILLER	CHECKED BY: A. GAMBLE				
																								BRATTLEBORO VT-9 EASTBOUND 2	SHEET 11 OF 175				