DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) (LB / FT) 1.75 1.88	SQUARE STEEL (IN) (LB / FT) 2.00 2.42	SQUARE STEEL (IN) (LB / FT) 2.50 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 7.60	TUBULAR STEEL Ø (IN) (LB / FT) 3.50 9.00	TUBULAR STEEL Ø (IN) (LB / FT) 4.00 10.80	TUBULAR STEEL Ø (IN) (LB / FT) 5.00 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
BRATTLEBORO EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		A	M1-5	24	24								1															
		A	VM-120	18	24						1		1							PAY FOR REMOVAL						TO BE SALVAGED TO BELOW THE NEW ROUTE MARKER SIGNS			
		A	M3-2	24	12		EAST / VERMONT 9	2.00								1		15.0' X								GREEN ON WHITE	X		
		A	M1-5	24	24			4.00																				E-136B
		A	VM-120	18	24		MOLLY STARK BYWAY					1														SALVAGE TO BELOW THE ROUTE MARKER SIGNS			
EB	3.409	A	R2-1	24	30		SPEED LIMIT 40						1		X													
		A	R2-1	24	30			5.00								1		13.5' X									X		
EB	3.503	A	R3-9b	24	36		CENTER LANE ONLY						1		X													
		A	R3-9b	24	36			6.00								1		13.5' X									X		
EB	3.576	A	R8-3A	24	24								1		X													
		A	R8-3A	24	24			4.00								1		12.0' X									X		
EB	3.805	A	R8-3A	24	24								1		X													
		A	R8-3A	24	24			4.00								1		14.75' X									X		
EB	3.894	A	R2-1	24	30		SPEED LIMIT 40 (MISSING)																			EXISTING SIGN IS MISSING			
		A	R2-1	24	30			5.00								1		15.0' X								INSTALL ~~260~~ 150 FT ± IN ADVANCE OF THE (3) BUSINESS SIGN ASSEMBLY AHEAD		6	
							SHEET TOTALS	30.00 SF	0.00 SF	0 EA	1 EA	1 EA	~~5~~ 6 EA	0 EA	0 EA	6 EA	~~90~~ 83.75 FT									
							TOWN DIRECTIONAL TOTALS	305.3	0.0	4.0	1.0	1.0	66	0.0	0.0	53	795.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **BRATTLEBORO EASTBOUND** PLOT DATE: **8/11/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
BRATTLEBORO VT-9 EASTBOUND 7 SHEET **16** OF **175**