DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
BRATTLEBORO WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	R2-1	24	30		SPEED LIMIT 40	5.00								1		13.0' X									X		
WB	2.757	F	R2-1	24	30		SPEED LIMIT 40 (MISSING)																			EXISTING SIGN AND POST ARE MISSING			
		F	R2-1	24	30			5.00								1		11.5' X								INSTALL 280 FT ± WEST OF THE DRIVE (ON LEFT) TO "RASHED'S GARDEN CENTER"	X		
WB	2.395	F	R2-1	24	30		SPEED LIMIT 50						1		X														
		F	R2-1	24	30			5.00								1		13.25' X								INSTALL ACROSS FROM ± THE EB SPEED LIMIT 40; THIS IS THE TRANSITION POINT	X		
WB	2.237	F	VW-202	36	36		TRUCKS ENTERING						1		X														
WB	1.980	F	M3-4	24	12		WEST						1		X														
		F	M1-5	24	24		VT-9						1																
WB	1.940	F	R2-1	24	30		SPEED LIMIT 50						1		X														
		F	D17-2	42	42		TRUCK LANE 2000 FT	12.25								2		14.75' 15.0' X								(NOTE:D17-2 IS THE FUTURE SHS SIGN CODE FOR THIS SIGN)		9	
WB	1.626	F	R4-6	24	30		TRUCK LANE 500 FT						1		X														
WB	1.525	F	R4-3	24	30		SLOWER TRAFFIC KEEP RIGHT						1		X														
WB	1.497	F	VW-285	30	30		FALLING ROCK SYMBOL			1				X												RETAIN			
WB	1.422	F	W9-1R	36	36		RIGHT LANE ENDS	9.00								2		14.25' 15.25' X								INSTALL 400 FT ± WEST OF THE FALLING ROCK SYMBOL	X		
WB	1.375	F	W9-1	36	36								1		X														
							SHEET TOTALS	36.25 SF	0.00 SF	1 EA	0 EA	0 EA	8 EA	0 EA	0 EA	7 EA		~~105~~ 97.0 FT											
							TOWN DIRECTIONAL TOTALS	268.5	0.0	2.0	1.0	1.0	64	0.0	0.0	47		705.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STPG SIGN (31)

FILE NAME: BRATTLEBORO WESTBOUND
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: M. MILLER
BRATTLEBORO VT-9 WESTBOUND 5

PLOT DATE: 8/11/2010
DRAWN BY: M. MILLER
CHECKED BY: A. GAMBLE