DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
BRATTLEBORO WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
WB	0.827	F	R2-1	24	30		SPEED LIMIT 50						1		X														
WB	0.762	F	W1-2R	30	30		RIGHT CURVE						1		X												A NEW WARNING SYMBOL TO BE INSTALLED JUST AHEAD			
		F	W13-1	18	18		40-MPH (PLAQUE)						1																
WB	~~0.709~~ 0.705	F	W1-4R	30	30			6.25								1		16.75' X								280 INSTALL ~~300~~ FT ± WEST OF THE PREVIOUS WARNING SIGN REMOVAL	X		
		F	W13-1	18	18			2.25																				X	
WB	0.650	F	W1-2L	30	30		LEFT CURVE SYMBOL						1		X														
		F	W13-1	18	18		40-MPH (PLAQUE)						1																
WB	0.608	E	W1-8	18	24								1		X														
		E	W1-8	24	30			5.00								1		14.0' X								FACES EB TRAFFIC	X		
WB	0.593	F	W1-6	48	24								1		X														
		E	W1-8	18	24								1																
		F	W1-6	48	24		(BACK-TO-BACK)	8.00								2		13.5' 14.5 X								LARGE ARROW FACES WB TRAFFIC	X		
		E	W1-8	24	30			5.00																		CHEVRON FACES EB TRAFFIC, INSTALLED ON BACK OF THE LARGE ARROW RIGHT-SIDE POST	X		
WB	0.558	F	W1-8	18	24								1		X														
		F	W1-8	24	30			5.00								1		13.5' X								FACES WB TRAFFIC	X		
							SHEET TOTALS	31.50	0.00	0	0	0	9	0	0	5		~~75~~ 72.25											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN DIRECTIONAL TOTALS	268.5	0.0	2.0	1.0	1.0	64	0.0	0.0	47		705.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **BRATTLEBORO WESTBOUND** PLOT DATE: **8/11/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
BRATTLEBORO VT-9 WESTBOUND 7 SHEET **26** OF **175**