DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
BRATTLEBORO WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
WB	0.348	F	W1-5R	30	30			6.25								2		13.25' X		NEW SIGN INSTALLED 150' EAST						NOTE CHANGE OF SYMBOL FROM EXISTING	X		
		F	W13-1	18	18			2.25																		NOTE CHANGE OF ADVISORY SPEED FROM EXISTING	X		
WB	0.231	F	W1-5R	30	30		RIGHT "WINDING ROAD" SYMBOL						1		X														
		F	W13-1	18	18		40-MPH (PLAQUE)						1																
SIGN SUMMARY SHEET VERMONT AGENCY OF TRANSPORTATION							SHEET TOTALS	8.50	0.00	0	0	0	2	0	0	2		~~30~~ 13.25											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN DIRECTIONAL TOTALS	268.5	0.0	2.0	1.0	1.0	64	0.0	0.0	47		705.0											

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STPG SIGN (31)

FILE NAME: BRATTLEBORO WESTBOUND
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: M. MILLER
BRATTLEBORO VT-9 WESTBOUND 9

PLOT DATE: 8/11/2010
DRAWN BY: M. MILLER
CHECKED BY: A. GAMBLE