DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
NEWFANE NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	1.488	A	M3-1	24	12								1		X													
		A	M1-5	24	24								1															
		A	M3-1	24	12		NORTH / VERMONT 30	2.00								1		13.5' X								GREEN ON WHITE	X	
		A	M1-5	24	24			4.00																				E-136B
NB	1.526	A	VW-619	30	30		SHOULDER NARROWS						1		X													
		A	VW-619	36	36			9.00								2		13.5' 14.0' X										5
NB	1.604	A	R2-1	24	30		SPEED LIMIT 40						1		X													
		A	R2-1	30	36			7.50								1		14.0' X								NOTE THAT NEW SIGN IS SLIGHTLY LARGER		6
NB	1.728	A	OM-3R	12	36		RIGHT OBJECT MARKER						~~1~~		~~X~~					SIGNS WERE REMOVED PRIOR TO THE PROJECT.						NOT WARRANTED		
NB	1.737	B	OM-3L	12	36		LEFT OBJECT MARKER						~~1~~		~~X~~											NOT WARRANTED		
NB	1.826	A	R2-1	24	30		SPEED LIMIT 40						1		X													
		A	R2-1	24	30			5.00								1		13.25' X									X	
NB	1.971	A	W1-4R	30	30		RIGHT REVERSE CURVE						1		X													
NB	2.004	A	W1-4R	30	30		0300 1312 0200	6.25								1		13.0' X								INSTALL 175 FT ± NORTH OF PREVIOUS POSITION	X	
NB	2.045	A	VW-054	30	30								1		X													
							SHEET TOTALS	33.75 SF	0.00 SF	0 EA	0 EA	0 EA	~~9~~ 7 EA	0 EA	0 EA	6 EA		~~90~~ 81.25 FT										
							TOWN DIRECTIONAL TOTALS	261.0	0.0	27.0	0.0	0.0	52	0.0	0.0	47		705.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STPG SIGN (31)

FILE NAME: NEWFANE NORTHBOUND
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: M. MILLER
NEWFANE VT-30 NORTHBOUND 3

PLOT DATE: 8/12/2010
DRAWN BY: M. MILLER
CHECKED BY: A. GAMBLE
SHEET 31 OF 175