








DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75	2.00	2.50	3.00	3.50	4.00	5.00			DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
																	(LB / FT)			(LB / FT)								
NEWFANE SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																"SHS"-STANDARD HIGHWAY SIGNS					
SB	5.277	F	W1-2R	30	30		RIGHT CURVE																INSTALL STOP SIGN ON A SEPARATE POST (MUTCD REQ) 5-10 FT ± IN ADVANCE OF THE DO NOT ENTER / ONE WAY SIGNS BELOW.					
		F	W13-1	18	18		40 MPH (PLAQUE)																INSTALL DO NOT ENTER AND ONE WAY SIGNS ON A SEPARATE POST, ACROSS FROM THE OTHER DO NOT ENTER / ONE WAY SIGNS					
SB	5.182 5.191	F	W1-4L	30	30			6.25															INSTALL ⁴⁵⁰ 500 FT ± SOUTH OF THE RIGHT CURVE SIGN THAT WAS JUST REMOVED	X				
		F	W13-1	18	18			2.25																	X			
SB	4.861	F	VW-054	30	30																							
		F	W16-2	30	18																							
		F	VW-054	30	30			6.25																		E-154		
		F	W16-2	24	18			3.00																	X			
SB	4.814	F	W1-2R	30	30		CURVE RIGHT																					
		F	W13-1	18	18		35 MPH PLAQUE																					
		F	W1-2R	30	30			6.25																	X			
		F	W13-1	18	18			2.25															NOTE THAT ADVISORY SPEED IS NOW 40 MPH		X			
SB	4.549	F	R2-5A	24	30			REDUCED SPEED AHEAD																				
		F	W3-5	36	36			9.00																	X			
SB	4.440	F	R2-1	24 30	30 36																							
SIGN SUMMARY SHEET							SHEET TOTALS	35.25	0.00	0	0	0	8	0	0	5	75 69.75							PROJECT NAME: STATEWIDE SOUTHEAST REGION PROJECT NUMBER: STPG SIGN (31)				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	284.2	0.0	23.0	2.0	2.0	55	0.0	0.0	50	750.0							FILE NAME: NEWFANE SOUTHBOUND PROJECT MANAGER: A. GAMBLE DESIGNED BY: M. MILLER NEWFANE VT-30 SOUTHBOUND 1	PLOT DATE: 8/12/2010 DRAWN BY: M. MILLER CHECKED BY: A. GAMBLE SHEET 38 OF 175			