






DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75	2.00	2.50	3.00	3.50	4.00	5.00			DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
																	(LB / FT)			(LB / FT)								
NEWFANE SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																"SHS"-STANDARD HIGHWAY SIGNS					
SB	4.440	F	R2-1	30	36			7.50							1	14.75' X							INSTALL STOP SIGN ON A SEPARATE POST (MUTCD REQ) 5 - 10 FT IN ADVANCE OF THE DO NOT ENTER / ONE WAY SIGNS BELOW.		6			
SB	4.336	F	W1-5L	30	30	FY		6.25							1	14.5' X							INSTALL DO NOT ENTER AND ONE WAY SIGNS ON A SEPARATE POST ACROSS FROM THE OTHER DO NOT ENTER / ONE WAY SIGNS	X				
SB	4.032	F	VD-062AL	72	16		BUSINESS DIRECTORY SIGN			1													Z POTS <===					
		F	VD-062B	72	16		BUSINESS DIRECTORY SIGN			1													WINDMILL HILL LOG CABIN AT <=== ALPACA FARM					
SB	3.985	F	D1-1A	72	10																		EXISTING SIGN AND POSTS MISSING					
		F	D1-1A	72	12			6.00							2	15.25' 16.75' X							INSTALL 175 FT ± IN ADVANCE OF THE NEXT (3) BUSINESS SIGN ASSEMBLY		4			
SB	3.952	F	VD-062B	72	16		BUSINESS DIRECTORY SIGN			1													KENOLIE VILLAGE <===					
		F	VD-062AL	72	16		BUSINESS DIRECTORY SIGN			1													WINCHESTER STABLES <===					
		F	VD-062B	72	16		BUSINESS DIRECTORY SIGN			1													WEST RIVER LODGE <===					
SB	3.848	F	M3-3S	24	12																							
		F	M1-5	24	24																							
		F	M3-3	24	12			2.00							1	13.5' X							GREEN ON WHITE	X				
		F	M1-5	24	24			4.00																		E-136B		
SB	3.806	F	VW-060	30	30																							
		F	VW-060	30	30			6.25							1	15.0' X											E-154	
SIGN SUMMARY SHEET							SHEET TOTALS	32.00	0.00	5	0	0	3	0	0	6	90- 89.75' FT							PROJECT NAME: STATEWIDE SOUTHEAST REGION PROJECT NUMBER: STPG SIGN (31)				
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	284.2	0.0	23.0	2.0	2.0	55	0.0	0.0	50	750.0							FILE NAME: NEWFANE SOUTHBOUND PROJECT MANAGER: A. GAMBLE DESIGNED BY: M. MILLER NEWFANE VT-30 SOUTHBOUND 2	PLOT DATE: 8/12/2010 DRAWN BY: M. MILLER CHECKED BY: A. GAMBLE SHEET 39 OF 175			