DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
NEWFANE SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
SB	1.156	F	W16-9	36	20		AHEAD (PLAQUE)						1													~~INSTALL STOP SIGN ON A SEPARATE POST (MUTCD REQ) 5 - 10 FT ± IN ADVANCE OF THE DO NOT ENTER / ONE WAY SIGNS BELOW;~~			
		F	S1-1	36	36	FYG		9.00								2		12.75' 13.25' X							~~INSTALL DO NOT ENTER AND ONE WAY SIGNS ON A SEPARATE POST, ACROSS FROM THE OTHER DO NOT ENTER / ONE WAY SIGNS~~	X		
		F	S4-3P	24	8	FYG		1.33																		SPAN THE PLAQUE ACROSS BOTH POSTS, CENTERED UNDER THE PRIMARY SIGN	X		
SB	1.118	F	D1-2	72	20		Newbrook ~~Newfane~~ Elementary School						2 ~~1~~		X											2 SIGNS WERE REMOVED AT THIS LOCATION			
		F	D1-2	72	20			10.00								2		13.0' 13.5' X										9	
SB	1.034	F	M3-3	24	12		SOUTH						1		X														
		F	M1-5	24	24		VERMONT 30						1																
SB	0.996	F	R2-1	24	30		0300 1312 0100 SPEED LIMIT 50						1		X														
SB	0.940	F	VD-062AS	72	16		BUSINESS DIRECTORY SIGN			1				X												OLALLIE DAYLILY GRDN. ===>			
SB	0.876	F	D1-1A	72	12						1		1		X											PAY FOR THE SALVAGED SIGNS TO BE REMOVED.			
		F	D1-1A	72	12						1		1																
		F	D1-1A	72	12		Williamsville 2 → South Newfane 4 →					1				2		13.5' 14.5' X								SALVAGE BOTH SIGNS ONTO A NEW SET OF POSTS			
		F	D1-1A	72	12							1																	
SB	0.840	G	VR-017	24	24		LEGAL LOAD LIMIT 24,000 POUNDS OVERWEIGHT PERMIT REQUIRED						2 ~~1~~		X											GRIMES HILL ROAD (TH-5)			
		G	VR-017	24	30			5.00								1		13.0' X								PERMIT SIGN SALVAGED ONTGO THE NEW POST.		6	
							SHEET TOTALS	25.33	0.00	1	3 ~~2~~	3 ~~2~~	10 ~~6~~	0	0	7		93.5' ~~105~~										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN DIRECTIONAL TOTALS	284.2	0.0	23.0	2.0	2.0	55	0.0	0.0	50		750.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STPG SIGN (31)

FILE NAME: NEWFANE SOUTHBOUND
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: M. MILLER
NEWFANE VT-30 SOUTHBOUND 7

PLOT DATE: 8/12/2010
DRAWN BY: M. MILLER
CHECKED BY: A. GAMBLE
SHEET 44 OF 175