DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
NEWFANE SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
																					(PAY FOR STOP SIGN REMOVAL ONLY)							
SB	0.832	H	R1-1	30	30		GRIMES HILL RD TH 5 STOP 0300 1312 0080			~~1~~	1	1	1	~~X~~	X	1					STREET SIGN WAS SALVAGED ONTO THE NEW POST ALSO MILE MARKER.					~~INSTALL STOP SIGN ON A SEPARATE POST (MUTCD REQ) 5 - 10 FT ± IN ADVANCE OF THE DO NOT ENTER / ONE WAY SIGNS BELOW;~~			
		H	R1-1	30	30			6.25								1		12.5' X								~~INSTALL DO NOT ENTER AND ONE WAY SIGNS ON A SEPARATE POST, ACROSS FROM THE OTHER DO NOT ENTER / ONE WAY SIGNS~~	X		
SB	0.812	F	M3-3	24	12		SOUTH VERMONT 30	2.00								1		13.5' X								**GREEN ON WHITE**	X		
		F	M1-5	24	24			4.00																		INSTALL 100 FEET ± SOUTH OF THE JCT WITH GRIMES HILL ROAD (TH-5)			E-136B
SB	0.802	F	R2-1	24	30		SPEED LIMIT 50	5.00								1		13.5' X								INSTALL 100 FEET ± SOUTH OF THE NEW ROUTE MARKER SIGNS ABOVE	X		
SB	0.570	G	R5-1	30	30								1		X											SEARS ROAD (TH-44) THIS ROAD IS A ONE-WAY EXIT			
		F	R6-1L	36	12						MISSING		~~1~~													THIS ASSEMBLY IS LOCATED ON THE NORTHERLY SIDE OF TH-44			
		E	R6-1R	36	12						MISSING		~~1~~															
		G	R5-1	30	30		DO NOT ENTER	6.25								1		13.25' X									X	
		F	R6-1L	36	12		ONE WAY ONE WAY	3.00																			X	
		E	R6-1R	36	12			3.00																			X	
SB	0.566	G	R5-1	30	30		DO NOT ENTER						1		X											SEARS ROAD (TH-44) THIS ROAD IS A ONE-WAY EXIT			
		H	R1-1	30	30		STOP						1															
		F	R6-1L	36	12		ONE WAY (LEFT ARROW)						1															
		E	R6-1R	36	12		ONE WAY (RIGHT ARROW)						1															
							SHEET TOTALS	29.50	0.00	1	~~0~~ 1	~~0~~ 1	~~7~~ 6	0	0	4		~~60~~ 52.75										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN DIRECTIONAL TOTALS	284.2	0.0	23.0	2.0	2.0	55	0.0	0.0	50		750.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STPG SIGN (31)

FILE NAME: NEWFANE SOUTHBOUND
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: M. MILLER
NEWFANE VT-30 SOUTHBOUND 8

PLOT DATE: 8/12/2010
DRAWN BY: M. MILLER
CHECKED BY: A. GAMBLE
SHEET 45 OF 175