DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
NEWFANE SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
SB	0.156	F	W16-8A	36	18								1													~~INSTALL STOP SIGN ON A SEPARATE POST (MUTCD REQ) 5 - 10 FT ± IN ADVANCE OF THE DO NOT ENTER / ONE WAY SIGNS BELOW;~~			
		F	W1-10L	36	36			9.00								2		15.25' 15.25' X							~~INSTALL DO NOT ENTER AND ONE WAY SIGNS ON A SEPARATE POST, ACROSS FROM THE OTHER DO NOT ENTER / ONE WAY SIGNS~~	X		
		F	W16-8	42	8		Williamsville Rd	2.33																		SPAN PLAQUE ACROSS BOTH POSTS		7	
SB	0.076	F	W11-2	30	30	FYG	PEDESTRIAN SYMBOL			1				X												AS-NEW; RETAIN ALL			
		F	W16-4	24	18	FYG	NEXT 600 FT (PLAQUE)			1																			
							SHEET TOTALS	11.33	0.00	2	0	0	1	0	0	2		~~30~~ 30.5											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN DIRECTIONAL TOTALS	284.2	0.0	23.0	2.0	2.0	55	0.0	0.0	50		750.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STPG SIGN (31)

FILE NAME: NEWFANE SOUTHBOUND
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: M. MILLER
NEWFANE VT-30 SOUTHBOUND 10

PLOT DATE: 8/12/2010
DRAWN BY: M. MILLER
CHECKED BY: A. GAMBLE