DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
TOWNSHEND NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	0.000	C	VD-024	60	7.5								1		X													
		C	VD-700	6	10								1															
		C	VD-700	6	10								1															
		C	VD-024	72	10		Townshend / Newfane	5.00								2		12.75' 13.0' X								REPLACE IN SAME LOCATION AS REMOVAL		4	
		C	VD-700	6	10		0300 1317 0000 / 0300 1312 0566	0.42																		TOWNSHEND MILE MARKER; INSTALL ON LEFT POST UNDER TOWNSHEND		4	
		C	VD-700	6	10			0.42																		NEWFANE MILE MARKER; INSTALL ON RIGHT POST UNDER NEWFANE		4	
NB	0.445	C	VR-017	24	30		LEGAL LOAD LIMIT 24,000 POUNDS			1			~~1~~	X	~~X~~											SING WAS DAMAGED IN SPRING 2011. IT WAS REPLACED BY THE STATE SIGN CREW IN EARLY AUGUST 2011			
		C	VR-017	24	30			~~5.00~~								~~1~~		~~X~~								ELLEN WARE RD (TH-33)		6	
NB	0.451	D	R1-1	30	30		STOP			1			~~1~~	X	~~X~~												REPLACED IN 2010 AS PART OF NEWFANE-TOWNSHEND STP2401(1)			
		D	R1-1	30	30			~~6.25~~								~~1~~		~~X~~									X		
NB	0.911	A	R2-5A	24	30		SPEED LIMIT 35 REDUCED SPEED AHEAD						~~1~~		~~X~~											OLD SIGN WAS MISSING			
		A	W3-5	36	36			9.00								2		14.0' 15.0' X									X		
NB	0.958	A	VD-018	30	18		Harmonyville Townshend 1						1		X															
		A	VD-018	30	18			3.75								1		13.0' X										8	
NB	0.973	C	VR-017	24	30		LEGAL LOAD LIMIT 24000 POUNDS			1				X												PLUMB ROAD (TH-32); NEWFANE-TOWNSHEND STP 2401(1) TO REPLACE IN 2010			
							SHEET TOTALS	~~18.59~~ ~~29.84~~ SF	0.00 SF	1 EA	0 EA	0 EA	~~4~~ ~~7~~ EA	0 EA	0 EA	7 EA	~~67.75'~~ ~~105~~ FT								
							TOWN DIRECTIONAL TOTALS	334.0	0.0	25.0	0.0	0.0	81	0.0	0.0	54	810.0								

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STPG SIGN (31)

FILE NAME: TOWNSHEND NORTHBOUND
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: M. MILLER
TOWNSHEND VT-30 NORTHBOUND 1

PLOT DATE: 8/12/2010
DRAWN BY: M. MILLER
CHECKED BY: A. GAMBLE