DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
TOWNSHEND NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	0.982	D	R1-1	30	30		0300 1317 0096 STOP			1				X												NEWFANE-TOWNSHEND STP 2401(1) TO REPLACE IN 2010			
NB	0.997	A	VW-054	30	30		HIDDEN DRIVE RIGHT						1		X											SIGHT DISTANCE TO DRIVE IS OK			
NB	1.050	A	R2-1	24	30		SPEED LIMIT 35						1		X														
		A	R2-1	30	36			7.50								1		13.5' X								NOTE LARGER SIZE		6	
NB	1.277	C	VR-017	24	30		SPEED LIMIT 30 LEGAL LOAD LIMIT 24000 POUNDS			~~2~~ 1				X												SAW DUST ALLEY (TH-70); NEWFANE TOWNSHEND STP 2401(1) TO REPLACE IN 2010			
NB	1.285	D	R1-1	30	30		0300 1317 0126 STOP			1				X												NEWFANE-TOWNSHEND STP 2401(1) TO REPLACE IN 2010			
NB	1.293	A	W2-1	30	30		OFFSET CROSSROAD (SYMBOL)						1		X											REMOVE ALL			
		A	W5-2	30	30		NARROW BRIDGE (TEXT)						1													NEXT ENTRY REFERENCING THIS REMOVAL POINT			
NB	1.306	A	W1-2L	30	30			6.25								1		14.25' X								INSTALL 70 FEET ± NORTH OF THE TWO-SIGN ASSEMBLY JUST REMOVED	X		
NB	1.333	A	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X														
NB	1.393	C	VR-017	24	30		LEGAL LOAD LIMIT 24000 POUNDS			1				X												EAST HILL ROAD (TH-25); NEWFANE-TOWNSHEND STP 2401(1) TO REPLACE IN 2010			
NB	1.399	D	R1-1	30	30		0300 1317 0140 STOP			1				X												NEWFANE-TOWNSHEND STP 2401(1) TO REPLACE IN 2010			
NB	1.527	A	VD-062B	72	16		BUSINESS DIRECTORY SIGN			1				X												GRACE COTTAGE HOSP. ===>			
		A	VD-062B	72	16		BUSINESS DIRECTORY SIGN			1				X												SECOND CHANCE ===>			
		A	VD-062B	72	16		BUSINESS DIRECTORY SIGN			1				X												OLD FARMHOUSE B&B ===>			
							SHEET TOTALS	13.75 SF	0.00 SF	8 EA	0 EA	0 EA	5 EA	0 EA	0 EA	2 EA		~~30~~ 27.75 FT										
							TOWN DIRECTIONAL TOTALS	334.0	0.0	25.0	0.0	0.0	81	0.0	0.0	54		810.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STPG SIGN (31)

FILE NAME: TOWNSHEND NORTHBOUND
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: M. MILLER
TOWNSHEND VT-30 NORTHBOUND 2

PLOT DATE: 8/12/2010
DRAWN BY: M. MILLER
CHECKED BY: A. GAMBLE