









DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS		EXISTING SIGNS				EXIST POST		NUMBER OF NEW POSTS	SQUARE STEEL (IN)			TUBULAR STEEL Ø (IN)				SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL		
								"A"	"B"	RETAIN	SALVAGE FROM	SALVAGE TO	REMOVE	RETAIN	REMOVE		1.75	2.00	2.50	3.00	3.50	4.00	5.00			DETAIL IN SHS	DETAIL ON SHEET NUMBER	DETAIL ON STD SHEET NUMBER
																	(LB / FT)			(LB / FT)								
<b>TOWNSHEND NB</b>							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN															"SHS"-STANDARD HIGHWAY SIGNS						
NB	1.547	A	R2-1	24	30			SPEED LIMIT 35																TO BE REPLACED FURTHER AHEAD				
NB	1.580	A	R2-1	24	30				5.00									15.0'	X					INSTALL BEHIND RAIL, 175 FT ± NORTH OF PREVIOUS POSITION	X			
NB	1.742	A	R2-5A	24	30			REDUCED SPEED AHEAD																ONLY A 5-MPH DROP IN SPEED LIMIT; SIGN WILL NOT BE REPLACED				
		A	W11-2	30	30	FYG			6.25									18.0'	X					INSTALL IN THE SAME POSITION AS THE JUST-REMOVED SPEED REDUCTION SIGN	X			
		A	W7-3A	24	18	FYG			3.00															FLUORESCENT YELLOW-GREEN SHEETING ON BOTH SIGNS	X			
NB	1.770	A	VD-018	30	18																						8	
		A	VD-018	30	18				3.75									12.25'	X									
NB	1.816	A	M4-11	24	12																							
		A	R8-3A	24	24																							
		A	VR-071	24	10																							
		A	VR-644P	24	12				2.00															BLACK ON WHITE			6	
		A	R8-3A	24	24				4.00																X			
		A	VR-071	24	10				1.67																		6	
NB	1.847	A	R2-1	24	30																							
		A	R2-1	30	36				7.50															NOTE LARGER SIZE			6	
<b>SIGN SUMMARY SHEET</b>							SHEET TOTALS		33.17	0.00	0	0	0	7	0	0	5								PROJECT NAME: STATEWIDE SOUTHEAST REGION			
							SF	SF	EA	EA	EA	EA	EA	EA	EA	EA	EA	FT							PROJECT NUMBER: STPG SIGN (31)			
							TOWN DIRECTIONAL TOTALS		334.0	0.0	25.0	0.0	0.0	81	0.0	0.0	54								FILE NAME: TOWNSHEND NORTHBOUND	PLOT DATE: 8/12/2010		
VERMONT AGENCY OF TRANSPORTATION																		810.0							PROJECT MANAGER: A. GAMBLE	DRAWN BY: M. MILLER		
																									DESIGNED BY: M. MILLER	CHECKED BY: A. GAMBLE		
																									TOWNSHEND VT-30 NORTHBOUND 3	SHEET 50 OF 175		