| DIRECTION | MILEPOINT | LOCATION CODE (SHEET 2) | SIGN CODE | WIDTH (IN) | HEIGHT (IN) | SHEETING REMARKS | SIGN LEGEND | NEW SIGNS "A" | NEW SIGNS "B" | EXISTING SIGNS RETAIN | EXISTING SIGNS SALVAGE FROM | EXISTING SIGNS SALVAGE TO | EXISTING SIGNS REMOVE | EXIST POST RETAIN | EXIST POST REMOVE | NUMBER OF NEW POSTS | SQUARE STEEL (IN) 1.75 (LB / FT) 1.88 | SQUARE STEEL (IN) 2.00 (LB / FT) 2.42 | SQUARE STEEL (IN) 2.50 (LB / FT) 3.35 | TUBULAR STEEL Ø (IN) FOUNDATION | TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60 | TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00 | TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80 | TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60 | SIGN FRAME REQUIRED | REMARKS | SIGN DETAIL: DETAIL IN SHS | SIGN DETAIL: DETAIL ON SHEET NUMBER | SIGN DETAIL: DETAIL ON STD SHEET NUMBER |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| **TOWNSHEND NB** | | | | | | | FY-FLUORESCENT YELLOW<br>FYG-FLUORESCENT YELLOW GREEN | | | | | | | | | | | | | | | | | | | "SHS"-STANDARD HIGHWAY SIGNS | | | |
| NB | 2.015 | A | M1-6 | 24 | 24 | | | | | | | | 1 | | | | | | | | | | | | | | | |
| | | A | M6-2 | 21 | 15 | | | | | | | | 1 | | | | | | | | | | | | | | | |
| | | A | M3-1 | 24 | 12 | | | 2.00 | | | | | | | | 2 | | 15.0'<br>15.0'<br>X | | | | | | #2 | GREEN ON WHITE | X | | |
| | | A | M1-5 | 24 | 24 | | | 4.00 | | | | | | | | | | | | | | | | | | | | E-136B |
| | | A | M6-2 | 21 | 15 | | | 2.19 | | | | | | | | | | | | | | | | | | | GREEN ON WHITE | X | | |
| | | A | M3-1 | 24 | 12 | | | 2.00 | | | | | | | | | | | | | | | | | | | BLACK ON WHITE | X | | |
| | | A | M1-6 | 24 | 24 | | | 4.00 | | | | | | | | | | | | | | | | | | | BLACK ON WHITE (NOT A STATE HIGHWAY) | | 9 | |
| | | A | M6-2 | 21 | 15 | | | 2.19 | | | | | | | | | | | | | | | | | | | BLACK ON WHITE | X | | |
| NB | 2.039 | A | S1-1 | 30 | 30 | FYG | | | | | | | 1 | | X | | | | | | | | | | | | | | | |
| | | A | W16-9 | 24 | 10 | FYG | | | | | | | 1 | | | | | | | | | | | | | | | | | |
| | | A | S1-1 | 30 | 30 | FYG | | 6.25 | | | | | | | | 1 | | 13.75'<br>X | | | | | | | | | FLUORESCENT YELLOW-GREEN SHEETING ON BOTH SIGNS | X | | |
| | | A | W16-9 | 24 | 12 | FYG |  | 2.00 | | | | | | | | | | | | | | | | | | | | X | | |
| NB | 2.055 | A | R8-3A | 24 | 24 | | | 4.00 | | | | | | | | 1 | | 12.5'<br>X | | | | | | | | | INSTALL BETWEEN TREE AND DRIVE TO LIBRARY; SOME TREE TRIMMING MIGHT BE REQUIRED? | X | | |
| | | A | VR-071 | 24 | 10 | | | 1.67 | | | | | | | | | | | | | | | | | | | 80 FEET ± NORTH OF "SCHOOL AHEAD" ASSEMBLY ABOVE | | 6 | |
| NB | 2.065 | A | S1-1 | 30 | 30 | FYG | | | | | | | 1 | | X | | | | | | | | | | | | | | | |
| | | | | | | | SHEET TOTALS | 30.30 | 0.00 | 0 | 0 | 0 | 5 | 0 | 0 | 4 | | 44.5 ~~60~~ | | | | | | | | | | | |
| | | | | | | | | SF | SF | EA | EA | EA | EA | EA | EA | EA | | FT | | | | | | | | | | | |
| | | | | | | | TOWN DIRECTIONAL TOTALS | 334.0 | 0.0 | 25.0 | 0.0 | 0.0 | 81 | 0.0 | 0.0 | 54 | | 810.0 | | | | | | | | | | | |

# SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **TOWNSHEND NORTHBOUND** PLOT DATE: **8/12/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
TOWNSHEND VT-30 NORTHBOUND 6 SHEET **53** OF **175**