DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
TOWNSHEND NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	2.065	A	W16-7	24	12	FYG							1																
		A	S1-1	30	30	FYG		6.25								1		14.0' X								NEXT TO SCHOOL CROSSWALK; FACING NB TRAFFIC	X		
		A	W16-7	24	12	FYG		2.00																		FLUORESCENT YELLOW-GREEN SHEETING ON BOTH SIGNS	X		
NB	2.066	B	S1-1	30	30	FYG							1		X														
		B	W16-7	24	12	FYG							1																
		B	S1-1	30	30	FYG		6.25								1		14.0' X								NEXT TO SCHOOL CROSSWALK; ANGLED TO FACE SB TRAFFIC	X		
		B	W16-7	24	12	FYG		2.00																		FLUORESCENT YELLOW-GREEN SHEETING ON BOTH SIGNS	X		
NB	2.079	D	R1-1	30	30		0300 1317 0205 STOP			1				X												GRAFTON ROAD (TH-1); NEWFANE-TOWNSHEND STP 2401(1) TO REPLACE IN 2010			
NB	2.081	A	R8-3A	24	24								1		X														
		A	D9-2	24	24		(BACK-TO-BACK)	4.00								1		15.75' X								INSTALL BACK-TO-BACK ON SAME POST; INSTALL IN SAME POSITION AS REMOVED NO PARKING SIGN	X		
		A	M6-1R	21	15			2.19																		WHITE ON BLUE (ALL FOUR SIGNS)	X		
		B	D9-2	24	24			4.00																			X		
		B	M6-1L	21	15		SEE NEXT SHEET	2.19	ARROW QUANTITY									SEE ALSO NEXT SHEET	NO PARKING WAS INSTALLED BELOW THE ARROW SIGN ON THE SAME POST.						X		
NB	2.083	A	D9-2	24	24		HOSPITAL						1		X														
		A	N/A	24	6		SKINNY ARROW RIGHT						1																
							SHEET TOTALS	28.88	0.00	1	0	0	6	0	0	3		~~45~~ 43.75										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN DIRECTIONAL TOTALS	334.0	0.0	25.0	0.0	0.0	81	0.0	0.0	54		810.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **TOWNSHEND NORTHBOUND** PLOT DATE: **8/12/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
TOWNSHEND VT-30 NORTHBOUND 7 SHEET **54** OF **175**