DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
TOWNSHEND NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	2.081	C ~~A~~	R8-3A	24	24			4.00							X	~~1~~		THIS NEW SIGN WAS INSTALLED AT NB MM 2.081 ~~X~~		SEE PREVIOUS SHEET.						INSTALL IN SAME POSITION AS THE REMOVED HOSPITAL SIGN CLOSEST TO ROUTE 30	X		
NB	2.083	B	D9-2	24	24		HOSPITAL						1		X											FACES SB TRAFFIC			
		B	N/A	24	6		SKINNY ARROW LEFT						1																
NB	2.083	D	R1-1	30	30		STOP	6.25		1				X				ON 8/15/2011 THIS POST AND SIGN WERE DESTROYED IN AN ACCIDENT. NEW POST AND SIGN WERE RE-INSTALLED AS PART OF THIS PROJECT. X 13.252'								NEWFANE-TOWNSHEND STP 2401(1) TO REPLACE IN 2010			
NB	2.092	D	R1-1	30	30		STOP			1				X												NEWFANE-TOWNSHEND STP 2401(1) TO REPLACE IN 2010			
NB	2.103	A	M3-1	24	12								1		X														
		A	M1-5	24	24								1																
		A	M3-1	24	12			2.00								1	13.75' X							GREEN ON WHITE	X		
		A	M1-5	24	24			4.00																					E-136B
NB	2.113	A	R8-3A	24	24								1		X														
		A	VR-122	24	10								1																
		A	R8-3A	24	24			4.00								1	14.0' X										X		
		A	VR-071	24	10			1.67																				6	
NB	2.130	C	VR-017	24	30		NO THRU TRAFFIC LLL 24K			1				X												COMMON ROAD (TH-53); NEWFANE-TOWNSHEND STP 2401(1) TO REPLACE IN 2010			
NB	2.138	D	R1-1	30	30		0300 1317 0211 STOP			1				X												NEWFANE-TOWNSHEND STP 2401(1) TO REPLACE IN 2010			
							SHEET TOTALS	~~21.92~~ ~~15.67~~	0.00	4	0	0	6	0	0	3	~~41.0~~ ~~45~~										
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT										
							TOWN DIRECTIONAL TOTALS	334.0	0.0	25.0	0.0	0.0	81	0.0	0.0	54	810.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **TOWNSHEND NORTHBOUND** PLOT DATE: **8/12/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
TOWNSHEND VT-30 NORTHBOUND 8 SHEET **55** OF **175**