DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
TOWNSHEND NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	2.141	A	S1-1	30	30	FYG							1		X													
		A	W16-7P	24	12	FYG							1															
		A	S1-1	30	30	FYG		6.25								1		14.0' X								FLUORESCENT YELLOW-GREEN SHEETING ON BOTH SIGNS	X	
		A	W16-7P	24	12	FYG		2.00																			X	
NB	2.170	A	R8-3A	24	24								1		X													
		A	VR-071	24	10								1															
		A	R8-3A	24	24			4.00								1		13.75' X									X	
		A	VR-071	24	10			1.67																				6
NB	2.215	A	VW-054	30	30								1		X													
		A	VW-054	30	30			6.25								1		10.25' X										E-154
NB	2.284	A	R2-1	24	30								1		X													
		A	R2-1	24	30			5.00								2		10.5' 11.75' X							# 1	INSTALL THE SPEED LIMIT SIGN ALONE ON THE RIGHT SIDE POST;	X	
		A	M4-6	24	12			2.00																		**BLACK ON WHITE**, INSTALL THE "END" PLAQUE ON TOP; THE NO PARKING SIGNS WILL BE ON THE	X	
		A	R8-3A	24	24			4.00																		LEFT-SIDE POST; USE A FRAME TO STABILIZE THE ASSEMBLY	X	
		A	VR-071	24	10			1.67																		**BLACK ON WHITE**, INSTALL BELOW THE NO PARKING SYMBOL		6
SIGN SUMMARY SHEET							SHEET TOTALS	32.84 SF	0.00 SF	0 EA	0 EA	0 EA	6 EA	0 EA	0 EA	5 EA	60.25 ~~75~~ FT										
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	334.0	0.0	25.0	0.0	0.0	81	0.0	0.0	54	810.0										

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **TOWNSHEND NORTHBOUND** PLOT DATE: **8/12/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
TOWNSHEND VT-30 NORTHBOUND 9 SHEET **56** OF **175**