DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
TOWNSHEND NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	2.334	A	M3-1	24	12								1		X														
		A	M1-5	24	24								1																
		A	M3-1	24	12			2.00								1		13.75' X							GREEN ON WHITE	X		
		A	M1-5	24	24			4.00																					E-136B
NB	2.426	A	VW-054	30	30		HIDDEN DRIVES RIGHT						1		X												TO BE REPLACED FURTHER AHEAD			
NB	2.474	A	R2-1	24	30								1		X															
		A	R2-1	24	30			5.00								1	12.75' X										X		
NB	2.498	A	VW-054	30	30			6.25								1	14.25' X									INSTALL 125 FEET ± NORTH OF THE SPEED LIMIT 50 SIGN			E-154
NB	2.903	A	VW-205	30	30		WATCH FOR TURNING VEHICLES						1		X														
NB	3.270	A	VW-285	36	36		FALLING ROCK (SYMBOL)			1				X													INSTALLED IN SUMMER 2007			
		A	W7-3A	30	18		NEXT 2 MILES (PLAQUE)			1																			
NB	3.306	A	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X														
NB	5.547	A	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X														
NB	5.902	C	VR-017	24	30		LEGAL LOAD LIMIT 24000 POUNDS			1				X													WINSLOW DRIVE (TH-22); NEWFANE-TOWNSHEND STP 2401(1) TO REPLACE IN 2010			
NB	5.908	D	R1-1	30	30		0300 1317 0588 STOP			1				X													NEWFANE-TOWNSHEND STP 2401(1) TO REPLACE IN 2010			
							SHEET TOTALS	17.25 SF	0.00 SF	4 EA	0 EA	0 EA	7 EA	0 EA	0 EA	3 EA	40.75 ~~45~~ FT									
							TOWN DIRECTIONAL TOTALS	334.0	0.0	25.0	0.0	0.0	81	0.0	0.0	54	810.0									

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **TOWNSHEND NORTHBOUND** PLOT DATE: **8/12/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
TOWNSHEND VT-30 NORTHBOUND 10 SHEET **57** OF **175**