DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
TOWNSHEND NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	6.161	A	R2-5A	24	30								1		X													
		A	W3-5	36	36			9.00								2		11.25' 13.25' X									X	
NB	6.200	A	VD-018	30	18								1		X													
		A	VD-018	30	18			3.75								1		12.0' X										8
NB	6.244	A	R2-1	24	30								1		X													
		A	R2-1	30	36			7.50								1		12.25' X									NOTE LARGER SIZE	6
NB	6.279	A	VD-062B	72	16		BUSINESS DIRECTORY SIGN			1				X													WINDHAM HILL INN ===>			
NB	6.369	A	R2-5A	24	30		REDUCED SPEED AHEAD						1		X													
		A	W3-5	36	36			9.00								2		8.5' 9.75' X										X	
NB	6.398	A	N/A	N/A	N/A		REMOVE EMPTY POST						1		X												SIGN IS MISSING; REMOVE EMPTY POST			
NB	6.408	A	VW-205	36	36			9.00								2		9.5' 11.0' X									INSTALL 50 FEET ± NORTH OF EMTPY POST REMOVAL			E-154
NB	6.453	A	R2-1	24	30								1		X													
		A	R2-1	30	36			7.50								1		13.25' X									NOTE LARGER SIZE		6	
NB	6.517	A	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X												BEHIND RAIL / FENCE ~ CAN ONLY ACCESS FROM PRIVATE PROPERTY TO REMOVE			
NB	6.531	A	W2-2MR	30	30		MODIFIED RIGHT SIDE ROAD SYMBOL						1		X												BEHIND RAIL / FENCE ~ CAN ONLY ACCESS FROM PRIVATE PROPERTY TO REMOVE			
							SHEET TOTALS	45.75	0.00	1	0	0	8	0	0	9		100.75 ~~135~~											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN DIRECTIONAL TOTALS	334.0	0.0	25.0	0.0	0.0	81	0.0	0.0	54		810.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **TOWNSHEND NORTHBOUND** PLOT DATE: **8/12/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
TOWNSHEND VT-30 NORTHBOUND 11 SHEET **58** OF **175**