DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
TOWNSHEND NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	6.540	C	VR-017	24	30		LEGAL LOAD LIMIT 24000 POUNDS			1				X												BACK WINDHAM RD (TH-7); NEWFANE-TOWNSHEND STP 2401(1) TO REPLACE IN 2010			
NB	6.550	D	R1-1	24	24		0300 1317 0652 STOP			1				X												NEWFANE-TOWNSHEND STP 2401(1) TO REPLACE IN 2010			
NB	6.567	A	R2-1	24	30		SPEED LIMIT 30						1		X														
		A	R2-1	24	30			5.00								1		11.25' X									X		
NB	6.585	A	D1-1A	54	7.5								1		X														
		A	D1-1A	72	12		Windham 7 →	6.00								2		11.0' 11.0' X										4	
NB	6.604	C	VR-017	24	30		LEGAL LOAD LIMIT 24000 POUNDS			1				X												WINDHAM HILL RD (TH-3); NEWFANE-TOWNSHEND STP 2401(1) TO REPLACE IN 2010			
NB	6.612	D	R1-1	30	30		0300 1317 0657 STOP			1				X												NEWFANE-TOWNSHEND STP 2401(1) TO REPLACE IN 2010			
NB	6.646	A	M3-1	24	12								1		X														
		A	M1-5	24	24								1																
		A	M3-1	24	12		NORTH	2.00								1		13.0' X								GREEN ON WHITE	X		
		A	M1-5	24	24		VERMONT 30	4.00																					E-136B
NB	6.675	A	R2-1	24	30		SPEED LIMIT 30						1		X														
		A	R2-1	24	30			5.00								1		13.25' X									X		
NB	6.828	A	R2-1	24	30								1		X														
SIGN SUMMARY SHEET							SHEET TOTALS	22.00	0.00	4	0	0	6	0	0	5		59.5 ~~75~~											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	334.0	0.0	25.0	0.0	0.0	81	0.0	0.0	54		810.0											

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STPG SIGN (31)

FILE NAME: TOWNSHEND NORTHBOUND
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: M. MILLER
TOWNSHEND VT-30 NORTHBOUND 12

PLOT DATE: 8/12/2010
DRAWN BY: M. MILLER
CHECKED BY: A. GAMBLE
SHEET 59 OF 175