DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
TOWNSHEND SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		F	VR-071	24	10			1.67																				6
SB	1.692	F	VD-062B	72	16		BUSINESS DIRECTORY SIGN			1				X												CAMPERAMA ===>		
SB	1.617	F	VD-018	30	18								1		X													
		F	VD-018	30	18			3.75								1		12.5' X									8
SB	1.546	F	R2-1	24	30		0300 1317 0160						1		X													
		F	R2-1	24	30			5.00								1		13.0' X								X	
SB	1.502	F	W5-2	30	30		NARROW BRIDGE						1		X													
		F	VW-060	30	30		HIDDEN DRIVES						1															
SB	1.448	G	VR-017	24	30		LEGAL LOAD LIMIT 24000 POUNDS			1				X												DEPOT ROAD (TH-35); NEWFANE-TOWNSHEND STP 2401(1) TO REPLACE IN 2010		
SB	1.444	H	R1-1	30	30		0300 1317 0143 STOP			1				X												NEWFANE-TOWNSHEND STP 2401(1) TO REPLACE IN 2010		
SB	1.078	F	W2-2R	30	30		RIGHT SIDE ROAD (SYMBOL)						1		X													
SB	1.048	F	R2-1	24	30								1		X													
		F	R2-1	24	30			5.00								1		13.0' X								X	
SB	0.827	G	VR-017	24	30		LEGAL LOAD LIMIT 24000 POUNDS			1				X												RIVERDALE ROAD (TH-55); NEWFANE-TOWNSHEND STP 2401(1) TO REPLACE IN 2010		
SB	0.817	H	R1-1	30	30		0300 1317 0082 STOP			1				X												NEWFANE-TOWNSHEND STP 2401(1) TO REPLACE IN 2010		
SIGN SUMMARY SHEET							SHEET TOTALS	15.42	0.00	5	0	0	6	0	0	3		38.5 ~~45~~										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	304.7	0.0	25.0	2.0	2.0	68	0.0	0.0	55		825.0										

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **TOWNSHEND SOUTHBOUND** PLOT DATE: **8/12/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
TOWNSHEND VT-30 SOUTHBOUND 10 SHEET **70** OF **175**