DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
ROCKINGHAM NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	1.520	B	VR-038	24	18		STATE HIGHWAY ENDS						1		X											SIGN IS ON BACK			
		A	R2-1	24	30		SPEED LIMIT 40						1															
		A	VR-041	24	24		THROUGH WAY BEGINS HERE						1															
		A	VR-039	24	18			3.00								1		13.0' X								INSTALL ON TOP		6	
		A	R2-1	24	30			5.00																			X		
NB	1.576	A	M3-1	24	12			2.00								1		13.75' X								INSTALL 5 TO 10 FT ± IN ADVANCE OF THE EXISTING SIGNS, DUE TO THE TREE	X		
		A	M1-4	24	24			4.00																			X		
NB	1.578	A	M3-1	24	12		NORTH						1		X														
		A	M1-4	24	24		US-5						1															
NB	1.852	A	VR-644P	24	12			2.00								1		14.0' X								INSTALL ON TOP. **BLACK LETTERS ON WHITE BACKGROUND.**		6	
		A	R8-3A	24	24			4.00																		INSTALL ACROSS FROM ± THE SB FACING "NO PARKING END" SIGNS	X		
NB	1.896	A	R8-3A	24	24		NO PARKING SYMBOL						1		X														
		A	N/A	12	18		BUS ROUTE SIGN (PVT)				~~X~~ 2		2													PRIVATE BUS ROUTE SIGN TO BE REMOVED AND SALVAGED - 2 SIGNS			
		A	R8-3A	24	24			4.00								1		13.0' X									X		
		A	N/A	12	18		BUS ROUTE SIGN (PVT)					~~1~~ 2														SALVAGE TO BELOW THE NEW NO PARKING SYMBOL			
SIGN SUMMARY SHEET							SHEET TOTALS	24.00	0.00	0	~~0~~ 2	~~1~~ 2	~~6~~ 8	0	0	4		~~60~~ 53.75										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	506.0	0.0	9.0	6.0	7.0	93	0.0	0.0	76		1140.0										

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **ROCKINGHAM NORTHBOUND** PLOT DATE: **8/13/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
ROCKINGHAM US-5 NORTHBOUND 1 SHEET **72** OF **175**