DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
ROCKINGHAM NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
NB	3.404	A	D1-1A	72	10								1		X														
		A	D1-1A	72	10								1																
		A	D1-1A	72	12			6.00								2		13.0' 13.0' X								4	
		A	D1-1A	72	12			6.00																		4	
NB	3.426	A	R2-1	24	30			5.00								1		15.0' X							INSTALL 100 FT± NORTH OF THE DESTINATION SIGN ASSEMBLY	X		
		A	R4-1	24	30			5.00																		THIS POSITION WILL BE MIDWAY BETWEEN ± THE SIGN ASSEMBLIES ABOVE AND BELOW	X		
NB	3.447	A	VD-062B	72	16		BUSINESS DIRECTORY SIGN			1				X												VERMED, INC. ===>			
		A	VD-062B	72	16		BUSINESS DIRECTORY SIGN			1				X												CHROMA ===>			
		A	VD-062B	72	16		BUSINESS DIRECTORY SIGN			1				X												SONNAX ===>			
NB	3.466	A	R8-3A	24	24		NO PARKING SYMBOL						1		X														
		A	M4-11	24	12		BEGIN (PLAQUE)						1																
		A	VR-644P	24	12			2.00								1		13.25' X							INSTALL ON TOP. **BLACK ON WHITE.**		6	
		A	R8-3A	24	24			4.00																			X		
NB	3.497	A	R8-3A	24	24								1		X														
		A	R8-3A	24	24			4.00								1		12.0' X									X		
SIGN SUMMARY SHEET							SHEET TOTALS	32.00	0.00	3	0	0	5	0	0	5		66.25 ~~75~~										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
VERMONT AGENCY OF TRANSPORTATION							TOWN DIRECTIONAL TOTALS	506.0	0.0	9.0	6.0	7.0	93	0.0	0.0	76		1140.0										

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **ROCKINGHAM NORTHBOUND** PLOT DATE: **8/13/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
ROCKINGHAM US-5 NORTHBOUND 7 SHEET **78** OF **175**