DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
ROCKINGHAM NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																		"SHS"-STANDARD HIGHWAY SIGNS			
NB	3.575	A	M4-6	24	12		END (PLAQUE)						1															
		A	M4-6	24	12		END	2.00								1		14.5' X							INSTALL PLAQUE ABOVE NO PARKING SYMBOL; **BLACK ON WHITE**	X		
		A	R8-3A	24	24			4.00																		X		
NB	3.700	A	R2-1	24	30		SPEED LIMIT 50						1		X													
		B	W14-3	48	36		NO PASSING PENNANT (ON BACK)						1															
NB	3.747 ~~3.737~~	A	VR-417	30	30		END NO PASSING BACK-TO-BACK NO PASSING ZONE	6.25								1		16.75' X							INSTALL THE END NO PASSING SIGN ON TOP, SPEED LIMIT 50 BELOW THAT, THE PENNANT WILL BE ON BACK		6	
		A	R2-1	24	30		SPEED LIMIT 50	5.00																	INSTALL 250 ~~175~~ FT± NORTH OF PREVIOUS POSITION, ACROSS FROM THE SB SPEED LIMIT 45 / DNP SIGNS	X		
		B	W14-3	48	36			5.56																	NO PASSING ZONE PENNANT IS INSTALLED ON THE BACK OF THE SPEED LIMIT SIGN	X		
NB	3.746	A	M2-1	21	15		JCT						1		X													
		A	M1-5	30	24		VT 10~~7~~ 3						1															
NB	3.779	A	M2-1	21	15		JCT	2.19								1		15.0' X							INSTALL 175 FT ± NORTH OF THE PREVIOUS POSITION. **GREEN ON WHITE**	X		
		A	M1-5	30	24		VERMONT 103	5.00																				E-136B
NB	3.815	A	VR-731	30	36		DOUBLE ARROW ONLY TURN LANES			1				X														
NB	3.856 ~~3.837~~	A	M3-1	24	12			2.00								2		~~X~~		SEE NOTE ON NEXT SHEET				#3A	SIGN FRAME REQUIRED (SEE E-123) **GREEN ON WHITE**	X		
		A	M1-5	30	24			5.00																	~~INSTALL THIS NEW ASSEMBLY 100 FT ± IN ADVANCE OF THE EXISTING ROUTE MARKER ASSEMBLY~~			E-136B
							SHEET TOTALS	37.00	0.00	1	0	0	5	0	0	5		46.25 ~~75~~										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN DIRECTIONAL TOTALS	506.0	0.0	9.0	6.0	7.0	93	0.0	0.0	76		1140.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **ROCKINGHAM NORTHBOUND**
PROJECT MANAGER: **A. GAMBLE**
DESIGNED BY: **M. MILLER**
PLOT DATE: **8/13/2010**
DRAWN BY: **M. MILLER**
CHECKED BY: **A. GAMBLE**