DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
ROCKINGHAM NB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		A	VM-120	18	24		CT RIVER BYWAY (PLAQUE)					1																
NB	3.960	A	M3-1	24	12		NORTH						1		X													
		A	M1-4	24	24		US 5						1															
		A	D6-4A	18	9		AMERICA'S BYWAYS				1		1													PAY FOR REMOVALS.			
		A	VM-120	18	24		CT RIVER BYWAY (PLAQUE)				1		1															
NB	3.983	A	R2-1	24	30		SPEED LIMIT 40						1		X													
NB	4.002	A	R2-1	24	30		SPEED LIMIT 40	5.00								1		13.75' X								INSTALL 100 FT ± NORTH OF PREVIOUS LOCATION	X		
NB	4.050	A	W1-2R	30	30		RIGHT CURVE						1		X											NOTE LOCATION OF REMOVAL AS REFERENCE FOR NEXT SIGN			
NB	4.107	A	W1-2R	30	30			6.25								2		16.0' 16.75' X								INSTALL 300 FT ± NORTH OF CURVE RIGHT SIGN THAT WAS REMOVED; 2 POST ASSEMBLY	X		
		A	VW-054R	30	30		HIDDEN DRIVE RIGHT	6.25																		BEHIND RAIL: **SOME BRUSH CUTTING LIKELY REQUIRED**			E-154
NB	4.215	A	W5-2	30	30		NARROW BRIDGES						1		X													
		A	VW-060	30	30		HIDDEN DRIVES						1															
		A	W5-2	30	30		NARROW BRIDGE	6.25								2		15.0' 15.0' X								INSTALL SIGNS ON A 2 POST ASSEMBLY	X		
		A	VW-054R	30	30		HIDDEN DRIVE RIGHT 0050 1314 0420	6.25																				E-154
NB	4.277	A	OM-3R	12	36								1		X													
							SHEET TOTALS	30.00	0.00	0	2	1	9 ~~7~~	0	0	5		~~76.5~~ ~~75~~										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN DIRECTIONAL TOTALS	506.0	0.0	9.0	6.0	7.0	93	0.0	0.0	76		1140.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **ROCKINGHAM NORTHBOUND** PLOT DATE: **8/13/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
ROCKINGHAM US-5 NORTHBOUND 12 SHEET **83** OF **175**