DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
ROCKINGHAM SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
SB	6.652	F	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X													
SB	5.833	F	VW-133L	30	30								1		X													
		F	VW-133L	30	30			6.25								1	14.0' X											E-154
SB	5.697	F	VW-133L	30	30								1		X													
		F	VW-133L	30	30			6.25								1	13.25' X											E-154
SB	5.610	F	W1-6L	48	24			8.00								2	12.0' 12.25' X										INSTALL 25 FT ± IN ADVANCE OF UTILITY POLE, IN ADVANCE OF HORSESHOE DRIVE ON LEFT	X		
SB	5.608	E	W1-6R	48	24			8.00								2	12.25' 12.75' X										THIS SIGN FACES NORTHBOUND TRAFFIC; INSTALL 10 FT ± SOUTH OF THE SOUTHBOUND-FACING SIGN	X		
SB	4.936	F	R2-5A	24	30		REDUCED SPEED AHEAD						1		X													
		F	W3-5	36	36			9.00								2	13.0' 14.0' X											X		
SB	4.874	F	W1-2R	30	30		RIGHT CURVE						1		X													
SB	4.828	F	R2-1	24	30								1		X													
		F	R2-1	~~30~~ 24	~~36~~ 30			7.50 ~~5.00~~								1	11.75' X										SEE E-MAIL, DATED 4/4/11, FROM A. GAMBLE, TRAFFIC OPS. NOTE LARGER SIZE	X		
SB	4.799	F	W1-10R	36	36			9.00								2	12.25' 13.5' X										INSTALL 150 FT ± SOUTH OF THE SPEED LIMIT 40 SIGN	X		
SB	4.718	F	N/A	30	30		HIDDEN DRIVE						1		X													
		F	W2-2	30	30			6.25								1	14.5' X											X		
							SHEET TOTALS	~~60.25~~ ~~57.75~~	0.00	0	0	0	7	0	0	12	~~155.5~~ ~~180~~												
								SF	SF	EA	EA	EA	EA	EA	EA	EA	FT												
							TOWN DIRECTIONAL TOTALS	442.6	0.0	9.0	3.0	3.0	78	0.0	0.0	73	1095.0												

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **ROCKINGHAM SOUTHBOUND** PLOT DATE: **8/13/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
ROCKINGHAM US-5 SOUTHBOUND 2 SHEET **89** OF **175**