DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
ROCKINGHAM SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
SB	3.252	E	W14-3	48	36				1																				
		F	R2-1	24	30		BACK-TO-BACK	5.00								1		15.0' X								X	
		F	R4-1	24	30			5.00																				X	
		E	W14-3	48	36			5.56																			THE PENNANT FACES NB TRAFFIC; INSTALL ON BACK OF THE SPEED LIMIT 45 SIGN	X	
SB	3.111	F	W2-3R	30	30			6.25								1		11.5' X									INSTALL 150 FT ± SOUTH OF PRIVATE SIGN "WHIPPOWILL GIFTS"	X	
SB	3.030	G	VR-017	24	30								1		X												ROCKINGHAM POST RD (TH-47)		
		G	VR-017	24	30			5.00								1		11.25' X											6
SB	3.030	H	R1-1	30	30		0050 1314 0308						1		X														
		H	R1-1	30	30			6.25								1		12.25' X									SKEWED INTERSECTION	X	
SB	2.888	F	VD-062AL	72	16		BUSINESS SIGN			1				X													WHITNEY <===		
SB	2.830	F	VD-062AS	72	16		BUSINESS SIGN			1				X													MORNING STAR ===>		
SB	2.758	F	R2-1	24	30		SPEED LIMIT 45						1		X														
		F	R4-1	24	30		DO NOT PASS						1																
SB	2.753	F	R2-1	24	30			5.00								1		15.0' X									SOUTH INSTALL BEHIND RAIL 25 FT ± ~~WEST~~ OF PREVIOUS POSITION, IF POSSIBLE	X	
		F	R4-1	24	30			5.00																			"DO NOT PASS" BELOW THE SPEED LIMIT SIGN	X	
							SHEET TOTALS	43.06	0.00	2	0	0	5	0	0	5		65.0 75										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN DIRECTIONAL TOTALS	442.6	0.0	9.0	3.0	3.0	78	0.0	0.0	73		1095.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **ROCKINGHAM SOUTHBOUND** PLOT DATE: **8/13/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
ROCKINGHAM US-5 SOUTHBOUND 9 SHEET **96** OF **175**