DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
ROCKINGHAM SB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
SB	2.588	G	VR-017	24	30								1		X											DARBY HILL ROAD (TH-46)			
		G	VR-017	24	30			5.00								1		12.5' X									6	
SB	2.578	H	R1-1	30	30								1		X														
		H	R1-1	30	30			6.25								1		13.0' X									X	
SB	2.558	F	M3-3	24	12			2.00								1		13.0' X								**BLACK ON WHITE**	X	
		F	M1-4	24	24			4.00																	INSTALL ASSEMBLY 100 FEET ± SOUTH OF THE DARBY HILL RD (TH-46) INTERSECTION	X	
SB	2.479	F	R2-1	24	30								1		X													
		F	W14-3	48	36								1															
		F	R2-1	24	30		BACK-TO-BACK	5.00								1		13.5' X									X	
		F	W14-3	48	36			5.56																	PENNANT FACES NB TRAFFIC AND IS INSTALLED ON BACK OF THE SPEED LIMIT SIGN	X	
SB	2.151	F	VD-062C	74.75	16		TRAVEL INFORMATION SIGN			1				X											SIGNS WERE FOUND ON THE GROUND. THEY WERE NOT PART OF THIS CONTRACT TO BE RE-INSTALLED.	RETAIN		
		F	VD-062C	74.75	16		TRAVEL INFORMATION SIGN			1																RETAIN		
SB	2.066	F	R2-5A	24	30		REDUCED SPEED AHEAD						1		X													
SB	2.012	F	W3-5	36	36			9.00								2		11.5' 12.25' X								INSTALL 285 FEET ± SOUTH OF THE "REDUCED SPEED AHEAD" SIGN THAT WAS JUST REMOVED	X	
SB	1.940	F	R2-1	24	30								1		X													

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN)
SHEET TOTALS	36.81	0.00	2	0	0	6	0	0	6	~~75.75~~ ~~90~~
	SF	SF	EA	EA	EA	EA	EA	EA	EA	FT
TOWN DIRECTIONAL TOTALS	442.6	0.0	9.0	3.0	3.0	78	0.0	0.0	73	1095.0

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **ROCKINGHAM SOUTHBOUND** PLOT DATE: **8/13/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
ROCKINGHAM US-5 SOUTHBOUND 10 SHEET **97** OF **175**