DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
CHESTER EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
EB	3.190	A	OM-3R	12	36								~~1~~		X											THIS BRIDGE DECK WAS REPLACED AND WIDENED RECENTLY. DUE TO THE WIDER SHOULDERS THE SIGNS WERE ALREADY REMOVED. NEW SIGNS WERE NOT NEEDED.			
		A	OM-3R	12	36			~~3.00~~								1		X									X		
EB	3.210	B	OM-3L	12	36								~~1~~		X											SEE ABOVE REMARKS			
		B	OM-3L	12	36			~~3.00~~								1		X									X		
EB	3.425	A	R2-1	24	30		SPEED LIMIT 50						1		X														
EB	3.400	A	W1-10L	36	36			9.00								2		13.5' 14.0' X								INSTALL 100 FT ± NORTH OF THE REMOVED SPEED LIMIT 50 SIGN	X		
							SHEET TOTALS	9.00 ~~15.00~~	0.00	0	0	0	1 ~~3~~	0	0	4		27.5 ~~60~~										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN DIRECTIONAL TOTALS	163.5	0.0	1.0	0.0	0.0	33	0.0	0.0	30		450.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: STATEWIDE SOUTHEAST REGION
PROJECT NUMBER: STPG SIGN (31)

FILE NAME: CHESTER EASTBOUND
PROJECT MANAGER: A. GAMBLE
DESIGNED BY: M. MILLER
CHESTER VT-10 EASTBOUND 5

PLOT DATE: 8/13/2010
DRAWN BY: M. MILLER
CHECKED BY: A. GAMBLE
SHEET 105 OF 175