DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
SPRINGFIELD EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
EB	0.000	C	VD-024	60	7.5								1		X														
		C	VD-700	6	8								1																
		C	VD-700	6	8								1																
		C	VD-024	72	10		Springfield / Chester	5.00								2		14.0' 14.0' X								TOWN LINE SIGN ON TOP; CENTER AND INSTALL THE ASSEMBLY IN THE SAME POSITION AS THE REMOVAL		4	
		C	VD-700	6	10		0100 1418 0000 / 0100 1407 0354	0.42																		INSTALL ON THE LEFT-SIDE POST UNDER "SPRINGFIELD"		4	
		C	VD-700	6	10			0.42																		INSTALL ON THE RIGHT-SIDE POST UNDER "CHESTER"		4	
EB	0.005	A	unknown	24	30		SPEED LIMIT 25 WITHIN SPRINGFIELD...						1		X											REMOVE ALL; THESE ARE ILLEGALLY INSTALLED WITHIN THE STATE HIGHWAY R.O.W.			
		A	unknown	24	30		NO OVERNIGHT PARKING...						1																
EB	0.020	A	unknown	24	12		NO TRUCKS						1		X											REMOVE; NOT A LEGAL SIGN			
EB	0.030	A	M3-2	24	12		EAST						1		X														
		A	M1-6	24	24		ROUTE 10 (BLACK & WHITE)						1																
		A	M6-2	21	15		ARROW 45 DEG LEFT (BLACK & WHITE)						1																
		A	M3-2	24	12		EAST	2.00								1		15.0' X								GREEN ON WHITE	X		
		A	M1-5	24	24		VERMONT 10	4.00																					E-136B
		A	M6-2L	21	15			2.19																		GREEN ON WHITE	X		
							SHEET TOTALS	14.03	0.00	0	0	0	9	0	0	3		43.0 ~~45~~										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN DIRECTIONAL TOTALS	146.7	0.0	7.0	0.0	0.0	35	0.0	0.0	22		330.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **SPRINGFIELD EASTBOUND** PLOT DATE: **8/13/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
SPRINGFIELD VT-10 EASTBOUND 1 SHEET **113** OF **175**