DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
SPRINGFIELD EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		~~A~~	~~VD-062AL~~	~~72~~	~~16~~		~~BUSINESS DIRECTORY SIGN~~			~~1~~																~~COGER'S SUGAR <===~~			
EB	0.555	A	W2-1	30	30			6.25								1		14.25' X								INSTALL 300 FT ± IN ADVANCE OF THE NEXT SET OF (3) BUSINESS SIGNS	X		
EB	0.620	A	VD-062B	72	16		BUSINESS DIRECTORY SIGN			1				X												VERMONT TIMBER ===>			
		A	VD-062B	72	16		BUSINESS DIRECTORY SIGN			1																HANCOR DRAINAGE ===>			
		A	VD-062AS	72	16		BUSINESS DIRECTORY SIGN			1																HOLIDAY INN ^UP			
EB	0.665	C	VR-079	24	30			5.00								1		12.5' X								COUNTY ROAD (TH-712)		6	
EB	0.675	D	R1-1	30	30		STOP (BACK-TO-BACK WITH)						1		X														
		C	VR-079	24	24		LEGAL LOAD AS FOR STATE HIGHWAY						1															
		D	R1-1	30	30			6.25								1		13.0' X									X		
EB	0.700	A	M4-6	24	12		END						1		X														
		A	M1-5	24	24		VT 10						1																
		A	M2-1	21	15		JCT						1																
		A	M1-5	30	24		VT 106						1																
		A	M4-6	24	12			2.00								2		14.75' 14.0' X								#1A GREEN ON WHITE	X		
		A	M1-5	24	24			4.00																					E-136B
							SHEET TOTALS	23.50	0.00	4	0	0	6	0	0	5		~~68.5~~ ~~75~~										
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT										
							TOWN DIRECTIONAL TOTALS	146.7	0.0	7.0	0.0	0.0	35	0.0	0.0	22		330.0										

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **SPRINGFIELD EASTBOUND** PLOT DATE: **8/13/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
SPRINGFIELD VT-10 EASTBOUND 3 SHEET **115** OF **175**