DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
SPRINGFIELD WB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
		G	M6-1	21	15		RIGHT ARROW (BLACK ON WHITE)		1																			
		G	M4-5	24	12		TO VERMONT 106	2.00								1		15.25' X								GREEN ON WHITE	X	
		G	M1-5	~~24~~ 30	24			5.00																		SIGN ASSEMBLY IS PARALLEL TO VT 10 WESTBOUND, FACING COUNTY ROAD (TH-712) ON THE LEFT			E-136B
		G	M6-1	21	15		0100 1418 0067	2.19																		GREEN ON WHITE	X	
WB	0.664	G	VR-017	24	24		LEGAL LOAD LIMIT 24,000 POUNDS						~~1~~		~~X~~						SIGN AND POST WERE MISSING					BALTIMORE ROAD (TH-8)			
		G	VR-017	24	30			5.00								1		12.25' X										6
WB	0.656	H	R1-1	30	30		STOP						1		X													
		H	R1-1	30	30			6.25								1		12.5' X									X	
WB	0.640	F	D2-1	72	10								1		X													
		F	D2-1	72	12		Gassets 4	6.00								2		17.25' 15.5' X										4
		F	M3-4	24	12		WEST VERMONT 10	2.00																		GREEN ON WHITE	X	
		F	M1-5	24	24			4.00																		INSTALL THE ROUTE MARKERS UNDER THE DESTINATION SIGN, ON THE LEFT-SIDE POST			E-136B
WB	0.600	F	R2-1	24	30		SPEED LIMIT 50						1		X													
		F	R2-1	24	30			5.00								1		13.25' X									X	
WB	0.002	F	R2-1	24	30		SPEED LIMIT 50						1		X													
							SHEET TOTALS	37.44 SF	0.00 SF	0 EA	0 EA	0 EA	~~5~~ 6 EA	0 EA	0 EA	6 EA			~~86.0~~ 90 FT									
							TOWN DIRECTIONAL TOTALS	66.9	0.0	3.0	0.0	0.0	13	0.0	0.0	11			165.0									

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **SPRINGFIELD WESTBOUND** PLOT DATE: **8/13/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
SPRINGFIELD VT-10 WESTBOUND 2 SHEET **120** OF **175**