DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WEATHERSFIELD EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
EB	3.522	A	M1-5	30	24				1																			
		A	M3-2	24	12			2.00								1	14.75' X								GREEN ON WHITE	X		
		A	M1-5	30	24			5.00																					E-136B
EB	3.580	A	R2-1	24	30				1						X														
		A	R2-1	24	30			5.00								1	15.75' X										X		
EB	3.745	A	W1-2R	30	30			6.25								1	14.75' X								INSTALL 150 FT ± IN ADVANCE OF JCT w/ HENRY GOULD RD (TH-65) ON LEFT	X		
EB	4.796	C	VR-017	24	30				1						X											GRAVELIN ROAD (TH-9)			
		C	VR-017	24	30			5.00								1	14.25' X											6	
EB	4.804	D	R1-1	30	30		1310 1420 0481		1						X														
		D	R1-1	30	30			6.25								1	14.75' X										X		
EB	4.826	A	VW-133	30	30				1						X														
		A	VW-133	30	30			6.25								1	13.0' X												E-154
EB	4.865	A	S3-1	30	30		SCHOOL BUS STOP AHEAD		1						X											SCHOOL BUS STOP AHEAD SIGN WILL NOT BE REPLACED			
		A	W11-7	30	30				1																				
		A	W11-7	30	30			6.25								1	13.0' X										X		
							SHEET TOTALS	42.00 SF	0.00 SF	0 EA	0 EA	0 EA	7 EA	0 EA	0 EA	7 EA	~~100.25~~ 105 FT												
							TOWN DIRECTIONAL TOTALS	778.3	0.0	47.0	9.0	9.0	180	0.0	0.0	108	1620.0												

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **WEATHERSFIELD EASTBOUND** PLOT DATE: **8/19/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
WEATHERSFIELD VT-131 EB 11 SHEET **132** OF **175**