DIRECTION	MILEPOINT	LOCATION CODE (SHEET 2)	SIGN CODE	WIDTH (IN)	HEIGHT (IN)	SHEETING REMARKS	SIGN LEGEND	NEW SIGNS "A"	NEW SIGNS "B"	EXISTING SIGNS RETAIN	EXISTING SIGNS SALVAGE FROM	EXISTING SIGNS SALVAGE TO	EXISTING SIGNS REMOVE	EXIST POST RETAIN	EXIST POST REMOVE	NUMBER OF NEW POSTS	SQUARE STEEL (IN) 1.75 (LB / FT) 1.88	SQUARE STEEL (IN) 2.00 (LB / FT) 2.42	SQUARE STEEL (IN) 2.50 (LB / FT) 3.35	TUBULAR STEEL Ø (IN) FOUNDATION	TUBULAR STEEL Ø (IN) 3.00 (LB / FT) 7.60	TUBULAR STEEL Ø (IN) 3.50 (LB / FT) 9.00	TUBULAR STEEL Ø (IN) 4.00 (LB / FT) 10.80	TUBULAR STEEL Ø (IN) 5.00 (LB / FT) 14.60	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL: DETAIL IN SHS	SIGN DETAIL: DETAIL ON SHEET NUMBER	SIGN DETAIL: DETAIL ON STD SHEET NUMBER
WEATHERSFIELD EB							FY-FLUORESCENT YELLOW FYG-FLUORESCENT YELLOW GREEN																			"SHS"-STANDARD HIGHWAY SIGNS			
EB	6.310	A	W1-4L	30	30			6.25								1		14.5' X								INSTALL BEHIND RAIL 25 FEET ± IN ADVANCE OF (WEST OF) THE SPEED LIMIT 50 SIGN	X		
EB	6.315	A	R2-1	24	30		SPEED LIMIT 50						1		X														
EB	6.545	A	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X														
EB	6.712	A	W1-4L	30	30		REVERSE CURVE LEFT						1		X												TO BE REPLACED FURTHER AHEAD			
		A	W13-1	18	18		35 MPH (PLAQUE)						1																
EB	6.792	A	W1-4L	30	30			6.25								1		16.0' X								INSTALL BEHIND RAIL 425 FT ± EAST OF THE PREVIOUS POSITION	X		
		A	W13-1	18	18			2.25																				X		
EB	7.210	A	VW-133	30	30		HIDDEN DRIVE LEFT						1		X														
		A	W11-7	30	30		EQUESTRIAN SYMBOL						1																
		A	W11-7	30	30			6.25								1		16.0' X								STILL VALID	X		
EB	7.246	A	W2-2R	30	30		RIGHT SIDE ROAD (SYMBOL)						1		X												TO BE REPLACED FURTHER AHEAD			
		A	VW-133	30	30			6.25								1		13.75' X								MAINTAIN 10 FT MIN TO UTILITY POLE; NOTE CHANGE TO **DRIVES**			E-154
EB	7.297	A	S3-1	30	30		SCHOOL BUS STOP AHEAD						1		X														
EB	7.325	A	W2-2R	30	30			6.25								1		16.75' X								INSTALL 150 FEET ± EAST OF THE JUST-REMOVED SCHOOL BUS STOP AHEAD SIGN	X		
EB	7.398	A	W3-5	36	36						1		1		X												PAY FOR REMOVAL			
							SHEET TOTALS	33.50	0.00	0	1	0	9 ~~8~~	0	0	5		77.0 ~~75~~											
								SF	SF	EA	EA	EA	EA	EA	EA	EA		FT											
							TOWN DIRECTIONAL TOTALS	778.3	0.0	47.0	9.0	9.0	180	0.0	0.0	108		1620.0											

SIGN SUMMARY SHEET

VERMONT AGENCY OF TRANSPORTATION

PROJECT NAME: **STATEWIDE SOUTHEAST REGION**
PROJECT NUMBER: **STPG SIGN (31)**

FILE NAME: **WEATHERSFIELD EASTBOUND** PLOT DATE: **8/19/2010**
PROJECT MANAGER: **A. GAMBLE** DRAWN BY: **M. MILLER**
DESIGNED BY: **M. MILLER** CHECKED BY: **A. GAMBLE**
WEATHERSFIELD VT-131 EB 14 SHEET **135** OF **175**